

Stormwater Memo

- 1.0 Introduction.** The proposal is to construct a 2 mW and 5 mW (AC) ground mount solar energy generating systems on a semi-active farm. This document presents existing and proposed construction as well as hydrologic conditions pre- and post-development.
- 2.0 Existing Conditions.** As shown on sheet C-1.0 Existing Conditions Plan, much of the overall parcel is a vacant and the proposed project is in an area that is under-utilized. The remainder of the parcel is forested areas and multiple ledge outcroppings.
- 3.0 Proposed Construction.** On the attached sheet C-3.0 layout and Materials Plan the solar system is laid out generally along the northerly portions of the three (3) parcels. Tree clearing and vegetation removal is planned. The following is some information about the system characteristics.

| Solar System Characteristics | 2 mW | 5 mW |
|-------------------------------------|--|-------------|
| Site Area: | 187.5± acres (84.1-2, 84.1-5.2, and 84.-1-6) | |
| Number of 385 w Modules: | 9,412 | 20,670 |
| Number of Central Inverters: | 1 | 2 |
| Height of Fence: | 7-foot | |
| Proposed Impervious area: | <1,000 sf (concrete pads) | |
| Proposed gravel roads: | 2.6 acres± | |
| Fenced area: | 13.16 acres | 28.39 acres |

The system is located on the vacant land with buffers (setbacks) maintained around the solar fields. The racking is low profile (9± feet high), does not generate noise, and has minimal impact on municipal services.

- 4.0 Stormwater.** There are only negligible (<1,000 square feet) new impervious surfaces (concrete equipment pads) associated with this project. The stormwater runoff from this site discharges in four (4) distinct locations in a hydrological study area of 130.2 acres.

4.1 Pre-Development Watersheds

The current conditions include strictly sheet flow from forested areas and cropland. Crops are primarily alfalfa, hay and similar grains. There are no known culverts or ditches. There are four (4) points of analysis. These are shown on the Pre-Development Watershed Plan.

4.2 Post-Development Watersheds

There are four (4) points of analysis. These are shown on the Post-Development Watershed Plan. Watershed areas and boundaries changed slightly due to the gravel roads, roadside swales (ditches), and road culverts.

Point of Analysis 1 (POA-1). This watershed area (24.6 acres) is to the far east of the overall hydrological area and on the east side of a north-side ridgeline. This watershed discharges to the southeasterly portion of the hydrological area in a small ravine. Runoff will continue to travel the same route in the post-development condition as it does now. There is less runoff in each of the modeled storms in the post-development condition.

Point of Analysis 2 (POA-2). This watershed area includes the majority (84.2 acres) of the overall hydrological area and the point of analysis is along the town/village line to the west edge of the project area. This tributary area decreased by 1.0 acres from the pre-development condition. Runoff will continue to travel a similar route as the pre-development condition. However, there are

swales and culverts associated with the new gravel road that are included in the Hydrocad analysis. There is less runoff in each of the modeled storms in the post-development condition.

Point of Analysis 3 (POA-3). This watershed area (12.5 acres) is to the far north central portion of the overall hydrological area. This tributary area increased by 4.0 acres due to the location of the road. This watershed discharges to northerly and off-site. Runoff will continue to travel the same route in the post-development condition as it does now, however it will travel in roadside swale and through a culvert. There is less runoff in each of the modeled storms in the post-development condition.

Point of Analysis 4 (POA-4). This watershed area (9.0 acres) is to the far south of the overall hydrological area and discharges via a roadside swale on the east side of Route 30. This tributary area decreased by 3.0 acres due to the location of the road. There is a proposed improvement to the CMP culvert under the existing dirt driveway. This location will be maintained as the permanent driveway for the solar project. Runoff will continue to travel the same route in the post-development condition as it does now, although it is captured in a proposed roadside swale.

4.3 Hydrocad Analysis

In order to determine the peak rate of discharge for existing and proposed conditions, runoff hydrographs using Hydrocad, were generated for the 2-, 10- and 100-year, 24-hour storm events using the Soil Conservation Service (SCS) Technical Release 20 Method NOAA/NRCC distribution.

As shown in Table 1 below, overall post-development peak stormwater runoff rates for the project are less than the pre-development peak stormwater runoff rates for the entire site. The four (4) design points are associated with the current topography of the site. Aside from the road grading and the 2-foot high landscape berm just south of the 2 mW solar system, there is no other grading. The overall watershed (hydrological study area) of 130.2 acres.

The hydrologic soil groups are primarily D type soils with some B type soils. See Hydrologic Soil Group figure attached. The cover types are “Meadow-continuous grass, protected from grazing and generally mowed for hay”, “Woods-Good”, and “Row crops, straight row, Good” for the existing conditions and “Meadow-continuous grass, protected from grazing and generally mowed for hay” and “Woods-Good” for the post-development condition. Additionally, the new gravel road (“Gravel Road”) is included in the post-development analysis.

The comparison of peak rates of runoff are shown in Table 1 below.

Table 1 Peak Stormwater Runoff Rates (in cfs)

| Design Point | Area (acres) | | 2-Year Storm (2.51 inches) | | | 10-Year Storm (3.64 inches) | | | 100-Year Storm (6.21 inches) | | |
|--------------|--------------|--------|----------------------------|------|-------|-----------------------------|------|-------|------------------------------|-------|--------|
| | Pre | Post | Pre | Post | Δ | Pre | Post | Δ | Pre | Post | Δ |
| POA-1 | 24.6 | 24.6 | 14.3 | 11.8 | (2.5) | 34.3 | 30.6 | (3.7) | 89.1 | 83.8 | (5.3) |
| POA-2 | 83.1 | 84.2 | 30.6 | 27.5 | (3.1) | 61.6 | 56.0 | (5.6) | 139.7 | 139.3 | (0.4) |
| POA-3 | 16.5 | 12.5 | 13.3 | 8.7 | (4.6) | 26.0 | 17.9 | (8.1) | 57.2 | 45.9 | (11.3) |
| POA-4 | 6.0 | 9.0 | 9.4 | 5.6 | (3.8) | 17.2 | 10.3 | (6.9) | 35.8 | 21.5 | (14.3) |
| | 130.2 | 130.3* | | | | | | | | | |

*Rounding error



PV Engineers, P.C.

A handwritten signature in blue ink that reads "David Albrecht". The signature is written in a cursive, flowing style.


David M. Albrecht, P.E.
Principal Civil Engineer

Solar Projects
117 Bliss Road
Schoharie, NY

FIGURES



| Schoharie County, New York (NY095) | | | |
|------------------------------------|--|--------------|----------------|
| Schoharie County, New York (NY095) | | | |
| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
| AI | Alluvial land | 4.0 | 2.9% |
| FaF | Farmington very rocky silt loam, 10 to 70 percent slopes | 0.8 | 0.6% |
| MhC | Mohawk and Honeoye soils, 10 to 20 percent slopes | 20.6 | 15.1% |
| MhD | Mohawk and Honeoye soils, 20 to 30 percent slopes | 4.5 | 3.3% |
| NdC | Nunda channery silt loam, 10 to 20 percent slopes | 0.0 | 0.0% |
| ShB | Schoharie and Hudson silt loams, 2 to 6 percent slopes | 64.6 | 47.5% |
| ShC | Schoharie and | 41.5 | 30.5% |





Date: 06/28/2018

FIGURE 1
NRCS Soils Survey-Soil Types
117 Bliss Road (NYS 30)
Schoharie, New York

Data Source: www.websoilssurvey.com



Borrego Solar
 Systems, Inc.
 55 Technology Drive
 Suite #102
 Lowell, MA 01851



Date: 06/28/2018

FIGURE 2
NRCS Soils Survey-Hydrologic Types
117 Bliss Road (NYS 30)
Schoharie, New York

Data Source: www.websoilssurvey.com




Borrego Solar
 Systems, Inc.
 55 Technology Drive
 Suite #102
 Lowell, MA 01851

APPENDIX A


Hydrocad Calculations



| ITEM | DATE | DESCRIPTION | STATUS |
|------|---------|-------------|----------------------------------|
| 1 | 7/3/18 | CS | DMA SUBMISSION TO PLANNING BOARD |
| 2 | 3/29/19 | CS | DMA SUBMISSION TO PLANNING BOARD |
| 3 | 6/5/19 | CS | DMA SUBMISSION TO PLANNING BOARD |
| 4 | 9/5/19 | CS | DMA TOWN BOARD RESUBMISSION |
| | | | |
| | | | |
| | | | |



PRE-DEVELOPMENT WATERSHED PLAN


SCALE: 1" = 200'





POST-DEVELOPMENT WATERSHED PLAN

SCALE: 1" = 200'



THIS DOCUMENT IS PROVIDED BY PV ENGINEERS, P.C. TO FACILITATE THE SALE AND INSTALLATION OF A SOLAR POWER SYSTEM FROM BORRERO SOLAR SYSTEMS, INC. REPRODUCTION, RELEASE OR UTILIZATION FOR ANY OTHER PURPOSE, WITHOUT PRIOR WRITTEN CONSENT IS STRICTLY PROHIBITED.

PV
Engineers

55 TECHNOLOGY DRIVE, SUITE 102
LOWELL, MA 01851
PHONE: (888) 898-6273
FAX: (888) 843-6778

NOT FOR
CONSTRUCTION


SITE USE PLANS
117 BLISS RD
SCHOHARIE, NY 12157

PROJECT NUMBER:
908-0999

| REV | DATE | DRAWN | CHECKED | RELEASE LEVEL |
|-----|---------|-------|---------|------------------------------|
| 1 | 7/3/18 | CS | DMA | SUBMISSION TO PLANNING BOARD |
| 2 | 3/29/19 | CS | DMA | SUBMISSION TO PLANNING BOARD |
| 3 | 6/5/19 | CS | DMA | SUBMISSION TO PLANNING BOARD |
| 4 | 9/5/19 | CS | DMA | TOWN BOARD RESUBMISSION |
| | | | | |
| | | | | |
| | | | | |

SCALES STATED ON DRAWINGS
ARE VALID ONLY WHEN PLOTTED
ARCH D 34" x 36"

W-2.0
POST-DEVELOPMENT
WATERSHED PLAN



Subcat 1




Southeast



Subcat 2



West



Subcat 3





North



Subcat 4



Route 30



Routing Diagram for 117 Bliss Rd NY_Hydrocad Pre_090419_D

Prepared by Borrego Solar Systems, Inc., Printed 9/6/2019
HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

117 Bliss Rd NY_Hydrocad Pre_090419_D

Prepared by Borrego Solar Systems, Inc.

Printed 9/6/2019

HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

| Area (acres) | CN | Description (subcatchment-numbers) |
|-----------------|-----------|---|
| 0.1 | 82 | Dirt roads, HSG B (2, 3) |
| 0.1 | 89 | Dirt roads, HSG D (3, 4) |
| 14.2 | 78 | Row crops, straight row, Good, HSG B (1, 2, 4) |
| 52.8 | 89 | Row crops, straight row, Good, HSG D (1, 2, 3, 4) |
| 12.0 | 55 | Woods, Good, HSG B (1, 2, 3) |
| 51.0 | 77 | Woods, Good, HSG D (1, 2, 3, 4) |
| 130.2 | 80 | TOTAL AREA |

117 Bliss Rd NY_Hydrocad Pre_090419_D

Prepared by Borrego Solar Systems, Inc.

Printed 9/6/2019

HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

Page 3

Soil Listing (all nodes)

| Area (acres) | Soil Group | Subcatchment Numbers |
|-----------------|---------------|-------------------------|
| 0.0 | HSG A | |
| 26.3 | HSG B | 1, 2, 3, 4 |
| 0.0 | HSG C | |
| 104.0 | HSG D | 1, 2, 3, 4 |
| 0.0 | Other | |
| 130.2 | | TOTAL AREA |

117 Bliss Rd NY_Hydrocad Pre_090419_D

Prepared by Borrego Solar Systems, Inc.

Printed 9/6/2019

HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

Page 4

Ground Covers (all nodes)

| HSG-A (acres) | HSG-B (acres) | HSG-C (acres) | HSG-D (acres) | Other (acres) | Total (acres) | Ground Cover | Subcatchment Numbers |
|------------------|------------------|------------------|------------------|------------------|------------------|-------------------------------|-------------------------|
| 0.0 | 0.1 | 0.0 | 0.1 | 0.0 | 0.2 | Dirt roads | 2, 3, 4 |
| 0.0 | 14.2 | 0.0 | 52.8 | 0.0 | 67.0 | Row crops, straight row, Good | 1, 2, 3, 4 |
| 0.0 | 12.0 | 0.0 | 51.0 | 0.0 | 63.0 | Woods, Good | 1, 2, 3, 4 |
| 0.0 | 26.3 | 0.0 | 104.0 | 0.0 | 130.2 | TOTAL AREA | |

Summary for Subcatchment 1: Subcat 1

Runoff = 14.3 cfs @ 12.16 hrs, Volume= 1.3 af, Depth= 0.61"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.4 | 78 | Row crops, straight row, Good, HSG B |
| 1.7 | 89 | Row crops, straight row, Good, HSG D |
| 4.8 | 55 | Woods, Good, HSG B |
| 17.7 | 77 | Woods, Good, HSG D |
| 24.6 | 74 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, |
| | | | | | Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, |
| | | | | | Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 2: Subcat 2

Runoff = 30.6 cfs @ 12.99 hrs, Volume= 6.6 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 82 | Dirt roads, HSG B |
| 12.1 | 78 | Row crops, straight row, Good, HSG B |
| 38.0 | 89 | Row crops, straight row, Good, HSG D |
| 5.6 | 55 | Woods, Good, HSG B |
| 27.4 | 77 | Woods, Good, HSG D |
| 83.1 | 81 | Weighted Average |
| 83.1 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, |
| | | | | | Woods: Light underbrush n= 0.400 P2= 2.51" |
| 26.5 | 1,723 | 0.0470 | 1.1 | | Shallow Concentrated Flow, |
| | | | | | Woodland Kv= 5.0 fps |
| 12.5 | 1,816 | 0.0725 | 2.4 | | Shallow Concentrated Flow, |
| | | | | | Cultivated Straight Rows Kv= 9.0 fps |
| 85.2 | 3,589 | Total | | | |

Summary for Subcatchment 3: Subcat 3

Runoff = 13.3 cfs @ 12.28 hrs, Volume= 1.4 af, Depth= 1.01"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 82 | Dirt roads, HSG B |
| 0.1 | 89 | Dirt roads, HSG D |
| 9.6 | 89 | Row crops, straight row, Good, HSG D |
| 1.6 | 55 | Woods, Good, HSG B |
| 5.2 | 77 | Woods, Good, HSG D |
| 16.5 | 82 | Weighted Average |
| 16.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 17.6 | 50 | 0.0020 | 0.0 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 5.7 | 421 | 0.0190 | 1.2 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 6.6 | 661 | 0.1100 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 2.2 | 220 | 0.0345 | 1.7 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 32.1 | 1,352 | Total | | | |

Summary for Subcatchment 4: Subcat 4

Runoff = 9.4 cfs @ 12.05 hrs, Volume= 0.6 af, Depth= 1.12"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 1.7 | 78 | Row crops, straight row, Good, HSG B |
| 3.5 | 89 | Row crops, straight row, Good, HSG D |
| 0.7 | 77 | Woods, Good, HSG D |
| 6.0 | 84 | Weighted Average |
| 6.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 4.0 | 50 | 0.0800 | 0.2 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 8.6 | 1,195 | 0.0660 | 2.3 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 12.6 | 1,245 | Total | | | |

Summary for Link POA 1: Southeast

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 0.61" for 2-Year event
 Inflow = 14.3 cfs @ 12.16 hrs, Volume= 1.3 af
 Primary = 14.3 cfs @ 12.16 hrs, Volume= 1.3 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: West

Inflow Area = 83.1 ac, 0.00% Impervious, Inflow Depth = 0.95" for 2-Year event
 Inflow = 30.6 cfs @ 12.99 hrs, Volume= 6.6 af
 Primary = 30.6 cfs @ 12.99 hrs, Volume= 6.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: North

Inflow Area = 16.5 ac, 0.00% Impervious, Inflow Depth = 1.01" for 2-Year event
 Inflow = 13.3 cfs @ 12.28 hrs, Volume= 1.4 af
 Primary = 13.3 cfs @ 12.28 hrs, Volume= 1.4 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 4: Route 30

Inflow Area = 6.0 ac, 0.00% Impervious, Inflow Depth = 1.12" for 2-Year event
 Inflow = 9.4 cfs @ 12.05 hrs, Volume= 0.6 af
 Primary = 9.4 cfs @ 12.05 hrs, Volume= 0.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Subcatchment 1: Subcat 1

Runoff = 34.3 cfs @ 12.15 hrs, Volume= 2.7 af, Depth= 1.34"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.4 | 78 | Row crops, straight row, Good, HSG B |
| 1.7 | 89 | Row crops, straight row, Good, HSG D |
| 4.8 | 55 | Woods, Good, HSG B |
| 17.7 | 77 | Woods, Good, HSG D |
| 24.6 | 74 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 2: Subcat 2

Runoff = 61.6 cfs @ 12.96 hrs, Volume= 12.6 af, Depth= 1.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 82 | Dirt roads, HSG B |
| 12.1 | 78 | Row crops, straight row, Good, HSG B |
| 38.0 | 89 | Row crops, straight row, Good, HSG D |
| 5.6 | 55 | Woods, Good, HSG B |
| 27.4 | 77 | Woods, Good, HSG D |
| 83.1 | 81 | Weighted Average |
| 83.1 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 26.5 | 1,723 | 0.0470 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 12.5 | 1,816 | 0.0725 | 2.4 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 85.2 | 3,589 | Total | | | |

Summary for Subcatchment 3: Subcat 3

Runoff = 26.0 cfs @ 12.27 hrs, Volume= 2.6 af, Depth= 1.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 82 | Dirt roads, HSG B |
| 0.1 | 89 | Dirt roads, HSG D |
| 9.6 | 89 | Row crops, straight row, Good, HSG D |
| 1.6 | 55 | Woods, Good, HSG B |
| 5.2 | 77 | Woods, Good, HSG D |
| 16.5 | 82 | Weighted Average |
| 16.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 17.6 | 50 | 0.0020 | 0.0 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 5.7 | 421 | 0.0190 | 1.2 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 6.6 | 661 | 0.1100 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 2.2 | 220 | 0.0345 | 1.7 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 32.1 | 1,352 | Total | | | |

Summary for Subcatchment 4: Subcat 4

Runoff = 17.2 cfs @ 12.04 hrs, Volume= 1.0 af, Depth= 2.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 1.7 | 78 | Row crops, straight row, Good, HSG B |
| 3.5 | 89 | Row crops, straight row, Good, HSG D |
| 0.7 | 77 | Woods, Good, HSG D |
| 6.0 | 84 | Weighted Average |
| 6.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 4.0 | 50 | 0.0800 | 0.2 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 8.6 | 1,195 | 0.0660 | 2.3 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 12.6 | 1,245 | Total | | | |

Summary for Link POA 1: Southeast

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 1.34" for 10-Year event
 Inflow = 34.3 cfs @ 12.15 hrs, Volume= 2.7 af
 Primary = 34.3 cfs @ 12.15 hrs, Volume= 2.7 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: West

Inflow Area = 83.1 ac, 0.00% Impervious, Inflow Depth = 1.82" for 10-Year event
 Inflow = 61.6 cfs @ 12.96 hrs, Volume= 12.6 af
 Primary = 61.6 cfs @ 12.96 hrs, Volume= 12.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: North

Inflow Area = 16.5 ac, 0.00% Impervious, Inflow Depth = 1.90" for 10-Year event
 Inflow = 26.0 cfs @ 12.27 hrs, Volume= 2.6 af
 Primary = 26.0 cfs @ 12.27 hrs, Volume= 2.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 4: Route 30

Inflow Area = 6.0 ac, 0.00% Impervious, Inflow Depth = 2.06" for 10-Year event
 Inflow = 17.2 cfs @ 12.04 hrs, Volume= 1.0 af
 Primary = 17.2 cfs @ 12.04 hrs, Volume= 1.0 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Subcatchment 1: Subcat 1

Runoff = 89.1 cfs @ 12.14 hrs, Volume= 6.9 af, Depth= 3.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.4 | 78 | Row crops, straight row, Good, HSG B |
| 1.7 | 89 | Row crops, straight row, Good, HSG D |
| 4.8 | 55 | Woods, Good, HSG B |
| 17.7 | 77 | Woods, Good, HSG D |
| 24.6 | 74 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 2: Subcat 2

Runoff = 139.7 cfs @ 12.94 hrs, Volume= 28.2 af, Depth= 4.08"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 82 | Dirt roads, HSG B |
| 12.1 | 78 | Row crops, straight row, Good, HSG B |
| 38.0 | 89 | Row crops, straight row, Good, HSG D |
| 5.6 | 55 | Woods, Good, HSG B |
| 27.4 | 77 | Woods, Good, HSG D |
| 83.1 | 81 | Weighted Average |
| 83.1 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 26.5 | 1,723 | 0.0470 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 12.5 | 1,816 | 0.0725 | 2.4 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 85.2 | 3,589 | Total | | | |

Summary for Subcatchment 3: Subcat 3

Runoff = 57.2 cfs @ 12.26 hrs, Volume= 5.8 af, Depth= 4.18"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 82 | Dirt roads, HSG B |
| 0.1 | 89 | Dirt roads, HSG D |
| 9.6 | 89 | Row crops, straight row, Good, HSG D |
| 1.6 | 55 | Woods, Good, HSG B |
| 5.2 | 77 | Woods, Good, HSG D |
| 16.5 | 82 | Weighted Average |
| 16.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|---|
| 17.6 | 50 | 0.0020 | 0.0 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 5.7 | 421 | 0.0190 | 1.2 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 6.6 | 661 | 0.1100 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 2.2 | 220 | 0.0345 | 1.7 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 32.1 | 1,352 | Total | | | |

Summary for Subcatchment 4: Subcat 4

Runoff = 35.8 cfs @ 12.04 hrs, Volume= 2.2 af, Depth= 4.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 1.7 | 78 | Row crops, straight row, Good, HSG B |
| 3.5 | 89 | Row crops, straight row, Good, HSG D |
| 0.7 | 77 | Woods, Good, HSG D |
| 6.0 | 84 | Weighted Average |
| 6.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 4.0 | 50 | 0.0800 | 0.2 | | Sheet Flow, Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 8.6 | 1,195 | 0.0660 | 2.3 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 12.6 | 1,245 | Total | | | |

Summary for Link POA 1: Southeast

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 3.36" for 100-Year event
 Inflow = 89.1 cfs @ 12.14 hrs, Volume= 6.9 af
 Primary = 89.1 cfs @ 12.14 hrs, Volume= 6.9 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: West

Inflow Area = 83.1 ac, 0.00% Impervious, Inflow Depth = 4.08" for 100-Year event
 Inflow = 139.7 cfs @ 12.94 hrs, Volume= 28.2 af
 Primary = 139.7 cfs @ 12.94 hrs, Volume= 28.2 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: North




Inflow Area = 16.5 ac, 0.00% Impervious, Inflow Depth = 4.18" for 100-Year event
 Inflow = 57.2 cfs @ 12.26 hrs, Volume= 5.8 af
 Primary = 57.2 cfs @ 12.26 hrs, Volume= 5.8 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 4: Route 30

Inflow Area = 6.0 ac, 0.00% Impervious, Inflow Depth = 4.39" for 100-Year event
 Inflow = 35.8 cfs @ 12.04 hrs, Volume= 2.2 af
 Primary = 35.8 cfs @ 12.04 hrs, Volume= 2.2 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs



Routing Diagram for 117 Bliss Rd NY_Hydrocad Post_090419_CS

Prepared by Borrego Solar Systems, Inc., Printed 9/6/2019
HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

117 Bliss Rd NY_Hydrocad Post_090419_CS

Prepared by Borrego Solar Systems, Inc.

Printed 9/6/2019

HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

Page 2

Area Listing (all nodes)

| Area (acres) | CN | Description (subcatchment-numbers) |
|-----------------|-----------|---|
| 2.8 | 48 | Brush, Good, HSG B (10, 20, 21, 22, 25) |
| 10.9 | 73 | Brush, Good, HSG D (10, 20, 21, 24, 25, 30, 31) |
| 0.1 | 89 | Dirt roads, HSG D (40) |
| 0.8 | 96 | Gravel surface, HSG B (20, 21, 22, 23, 24, 25, 30) |
| 1.8 | 96 | Gravel surface, HSG D (20, 22, 23, 24, 25, 30, 31, 40) |
| 4.7 | 58 | Meadow, non-grazed, HSG B (20, 21, 22, 23, 24) |
| 37.4 | 78 | Meadow, non-grazed, HSG D (10, 20, 21, 22, 23, 24, 25, 30, 31) |
| 0.0 | 98 | Paved parking, HSG B (24) |
| 0.0 | 98 | Paved parking, HSG D (20, 22, 23, 24) |
| 8.5 | 78 | Row crops, straight row, Good, HSG B (20, 21, 22, 23, 25, 30, 40) |
| 24.8 | 89 | Row crops, straight row, Good, HSG D (10, 20, 21, 22, 23, 25, 30, 31, 40) |
| 9.3 | 55 | Woods, Good, HSG B (10, 20, 21, 22, 25, 30, 40) |
| 28.9 | 77 | Woods, Good, HSG D (10, 20, 21, 22, 25, 30, 40) |
| 130.2 | 77 | TOTAL AREA |

Soil Listing (all nodes)

| Area (acres) | Soil Group | Subcatchment Numbers |
|-----------------|---------------|--|
| 0.0 | HSG A | |
| 26.3 | HSG B | 10, 20, 21, 22, 23, 24, 25, 30, 40 |
| 0.0 | HSG C | |
| 103.9 | HSG D | 10, 20, 21, 22, 23, 24, 25, 30, 31, 40 |
| 0.0 | Other | |
| 130.2 | | TOTAL AREA |

Ground Covers (all nodes)

| HSG-A (acres) | HSG-B (acres) | HSG-C (acres) | HSG-D (acres) | Other (acres) | Total (acres) | Ground Cover | Subcatchment Numbers |
|------------------|------------------|------------------|------------------|------------------|------------------|-------------------------------|---------------------------------------|
| 0.0 | 2.8 | 0.0 | 10.9 | 0.0 | 13.8 | Brush, Good | 10, 20, 21, 22, 24, 25, 30, 31 |
| 0.0 | 0.0 | 0.0 | 0.1 | 0.0 | 0.1 | Dirt roads | 40 |
| 0.0 | 0.8 | 0.0 | 1.8 | 0.0 | 2.7 | Gravel surface | 20, 21, 22, 23, 24, 25, 30, 31, 40 |
| 0.0 | 4.7 | 0.0 | 37.4 | 0.0 | 42.1 | Meadow, non-grazed | 10, 20, 21, 22, 23, 24, 25, 30, 31 |
| 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | Paved parking | 20, 22, 23, 24 |
| 0.0 | 8.5 | 0.0 | 24.8 | 0.0 | 33.3 | Row crops, straight row, Good | 10, 20, 21, 22, 23, 25, 30, 31, 40 |
| 0.0 | 9.3 | 0.0 | 28.9 | 0.0 | 38.2 | Woods, Good | 10, 20, 21, 22, 25, 30, 40 |
| 0.0 | 26.3 | 0.0 | 103.9 | 0.0 | 130.2 | TOTAL AREA | |

117 Bliss Rd NY_Hydrocad Post_090419_CS

Prepared by Borrego Solar Systems, Inc.

Printed 9/6/2019

HydroCAD® 10.00-24 s/n 08380 © 2018 HydroCAD Software Solutions LLC

Page 5

Pipe Listing (all nodes)

| Line# | Node Number | In-Invert (feet) | Out-Invert (feet) | Length (feet) | Slope (ft/ft) | n | Diam/Width (inches) | Height (inches) | Inside-Fill (inches) |
|-------|----------------|---------------------|----------------------|------------------|------------------|-------|------------------------|--------------------|-------------------------|
| 1 | 20P | 681.50 | 681.00 | 35.0 | 0.0143 | 0.012 | 12.0 | 0.0 | 0.0 |
| 2 | 22P | 728.20 | 727.80 | 35.0 | 0.0114 | 0.012 | 18.0 | 0.0 | 0.0 |
| 3 | 23P | 706.00 | 704.50 | 31.0 | 0.0484 | 0.012 | 12.0 | 0.0 | 0.0 |
| 4 | 24P | 821.00 | 820.50 | 57.0 | 0.0088 | 0.012 | 12.0 | 0.0 | 0.0 |
| 5 | 25P | 733.50 | 733.00 | 25.0 | 0.0200 | 0.012 | 12.0 | 0.0 | 0.0 |
| 6 | 31P | 806.00 | 805.70 | 25.0 | 0.0120 | 0.012 | 12.0 | 0.0 | 0.0 |
| 7 | 40P | 663.10 | 662.30 | 95.0 | 0.0084 | 0.012 | 12.0 | 0.0 | 0.0 |

Summary for Subcatchment 10:

Runoff = 11.8 cfs @ 12.17 hrs, Volume= 1.1 af, Depth= 0.53"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.1 | 48 | Brush, Good, HSG B |
| 3.1 | 73 | Brush, Good, HSG D |
| 3.7 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.1 | 55 | Woods, Good, HSG B |
| 12.6 | 77 | Woods, Good, HSG D |
| 24.6 | 72 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, |
| | | | | | Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, |
| | | | | | Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 20:

Runoff = 18.5 cfs @ 12.47 hrs, Volume= 2.6 af, Depth= 0.79"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.8 | 48 | Brush, Good, HSG B |
| 5.1 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.6 | 96 | Gravel surface, HSG D |
| 0.7 | 58 | Meadow, non-grazed, HSG B |
| 9.0 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 5.0 | 78 | Row crops, straight row, Good, HSG B |
| 8.3 | 89 | Row crops, straight row, Good, HSG D |
| 1.0 | 55 | Woods, Good, HSG B |
| 8.3 | 77 | Woods, Good, HSG D |
| 38.9 | 78 | Weighted Average |
| 38.9 | | 99.98% Pervious Area |
| 0.0 | | 0.02% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 30.7 | 50 | 0.0010 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 4.8 | 580 | 0.0840 | 2.0 | | Shallow Concentrated Flow, Solar Area Short Grass Pasture Kv= 7.0 fps |
| 9.7 | 550 | 0.0360 | 0.9 | | Shallow Concentrated Flow, Stumps Remain Woodland Kv= 5.0 fps |
| 45.2 | 1,180 | Total | | | |

Summary for Subcatchment 21:

Runoff = 3.4 cfs @ 12.25 hrs, Volume= 0.4 af, Depth= 0.61"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.3 | 48 | Brush, Good, HSG B |
| 1.0 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 0.7 | 78 | Meadow, non-grazed, HSG D |
| 1.2 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 0.8 | 55 | Woods, Good, HSG B |
| 2.8 | 77 | Woods, Good, HSG D |
| 7.0 | 74 | Weighted Average |
| 7.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 17.6 | 50 | 0.0040 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 1.0 | 71 | 0.0300 | 1.2 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.2 | 474 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 0.5 | 64 | 0.1100 | 2.3 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.0 | 564 | 0.0250 | 2.4 | | Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps |
| 27.3 | 1,223 | Total | | | |

Summary for Subcatchment 22:

Runoff = 27.3 cfs @ 12.10 hrs, Volume= 1.9 af, Depth= 1.01"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 48 | Brush, Good, HSG B |
| 0.1 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 1.0 | 58 | Meadow, non-grazed, HSG B |
| 8.5 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 10.8 | 89 | Row crops, straight row, Good, HSG D |
| 0.0 | 55 | Woods, Good, HSG B |
| 2.2 | 77 | Woods, Good, HSG D |
| 23.0 | 82 | Weighted Average |
| 23.0 | | 100.00% Pervious Area |
| 0.0 | | 0.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 5.3 | 50 | 0.0800 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 8.1 | 807 | 0.0560 | 1.7 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.8 | 403 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.2 | 1,260 | Total | | | |

Summary for Subcatchment 23:

Runoff = 1.8 cfs @ 12.07 hrs, Volume= 0.1 af, Depth= 0.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 96 | Gravel surface, HSG B |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.9 | 58 | Meadow, non-grazed, HSG B |
| 1.3 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.7 | 67 | Weighted Average |
| 4.7 | | 99.80% Pervious Area |
| 0.0 | | 0.20% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 4.9 | 50 | 0.0980 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 3.8 | 402 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.1 | 304 | 0.0130 | 1.6 | 4.9 | Trap/Vee/Rect Channel Flow, Roadside swale Bot.W=1.00' D=1.00' Z= 2.0 ' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 11.8 | 756 | Total | | | |

Summary for Subcatchment 24:

Runoff = 3.8 cfs @ 12.19 hrs, Volume= 0.3 af, Depth= 0.79"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|---------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 5.1 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG B |
| 0.0 | 98 | Paved parking, HSG D |
| 5.2 | 78 | Weighted Average |
| 5.2 | | 99.73% Pervious Area |
| 0.0 | | 0.27% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 10.7 | 50 | 0.0140 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 13.1 | 1,227 | 0.0500 | 1.6 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 23.8 | 1,277 | Total | | | |

Summary for Subcatchment 25:

Runoff = 0.8 cfs @ 12.18 hrs, Volume= 0.1 af, Depth= 0.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.7 | 48 | Brush, Good, HSG B |
| 0.7 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.3 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 2.7 | 55 | Woods, Good, HSG B |
| 0.5 | 77 | Woods, Good, HSG D |
| 5.4 | 63 | Weighted Average |
| 5.4 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 11.8 | 50 | 0.0300 | 0.1 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 1.2 | 80 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 4.5 | 500 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 1.0 | 103 | 0.1200 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 18.5 | 733 | Total | | | |

Summary for Subcatchment 30:

Runoff = 5.9 cfs @ 12.21 hrs, Volume= 0.6 af, Depth= 0.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 5.4 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.1 | 89 | Row crops, straight row, Good, HSG D |
| 0.4 | 55 | Woods, Good, HSG B |
| 1.8 | 77 | Woods, Good, HSG D |
| 9.0 | 77 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 8.9 | 50 | 0.0220 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 16.7 | 1,540 | 0.0480 | 1.5 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 25.6 | 1,590 | Total | | | |

Summary for Subcatchment 31:

Runoff = 3.1 cfs @ 12.11 hrs, Volume= 0.2 af, Depth= 0.79"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.1 | 96 | Gravel surface, HSG D |
| 3.4 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 3.5 | 78 | Weighted Average |
| 3.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 11.4 | 50 | 0.0120 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 6.1 | 396 | 0.0240 | 1.1 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.5 | 446 | Total | | | |

Summary for Subcatchment 40:

Runoff = 5.6 cfs @ 12.64 hrs, Volume= 0.9 af, Depth= 1.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 2-Year Rainfall=2.51"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.0 | 78 | Row crops, straight row, Good, HSG B |
| 5.6 | 89 | Row crops, straight row, Good, HSG D |
| 0.3 | 55 | Woods, Good, HSG B |
| 0.8 | 77 | Woods, Good, HSG D |
| 9.0 | 85 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 2.7 | 180 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 10.4 | 1,500 | 0.0710 | 2.4 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 1.0 | 188 | 0.0500 | 3.2 | 9.7 | Trap/Vee/Rect Channel Flow, Roadside Swale Bot.W=1.00' D=1.00' Z= 2.0 '/' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 60.3 | 1,918 | Total | | | |

Summary for Reach 20R-G: Grass

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 0.76" for 2-Year event
 Inflow = 13.0 cfs @ 14.10 hrs, Volume= 3.2 af
 Outflow = 13.0 cfs @ 14.14 hrs, Volume= 3.2 af, Atten= 0%, Lag= 2.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.8 fps, Min. Travel Time= 1.6 min
 Avg. Velocity = 0.9 fps, Avg. Travel Time= 3.1 min

Peak Storage= 1,238 cf @ 14.11 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 2.0' Flow Area= 400.0 sf, Capacity= 5,078.6 cfs

100.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 300.00'
 Length= 169.0' Slope= 0.0609 '/'
 Inlet Invert= 679.00', Outlet Invert= 668.70'



Summary for Reach 20R-S: Swale

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 0.76" for 2-Year event
 Inflow = 13.0 cfs @ 14.07 hrs, Volume= 3.2 af
 Outflow = 13.0 cfs @ 14.10 hrs, Volume= 3.2 af, Atten= 0%, Lag= 1.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.4 fps, Min. Travel Time= 0.4 min
 Avg. Velocity = 1.3 fps, Avg. Travel Time= 0.8 min

Peak Storage= 345 cf @ 14.09 hrs
 Average Depth at Peak Storage= 0.9'
 Bank-Full Depth= 2.0' Flow Area= 18.0 sf, Capacity= 66.5 cfs

3.00' x 2.00' deep channel, n= 0.078 Riprap, 12-inch
 Side Slope Z-value= 3.0 '/' Top Width= 15.00'
 Length= 64.0' Slope= 0.0313 '/'
 Inlet Invert= 681.00', Outlet Invert= 679.00'



Summary for Reach 23R: Crops

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 0.61" for 2-Year event
 Inflow = 3.2 cfs @ 12.31 hrs, Volume= 0.4 af
 Outflow = 2.5 cfs @ 12.70 hrs, Volume= 0.4 af, Atten= 22%, Lag= 23.2 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.9 fps, Min. Travel Time= 13.3 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 24.7 min

Peak Storage= 2,015 cf @ 12.47 hrs
 Average Depth at Peak Storage= 0.0'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,304.4 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 200.00'
 Length= 752.0' Slope= 0.0616 '/'
 Inlet Invert= 727.80', Outlet Invert= 681.50'



Summary for Reach 23R-G: Grass

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.36" for 2-Year event
 Inflow = 1.6 cfs @ 12.19 hrs, Volume= 0.1 af
 Outflow = 1.5 cfs @ 12.27 hrs, Volume= 0.1 af, Atten= 4%, Lag= 4.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.1 fps, Min. Travel Time= 2.8 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 5.8 min

Peak Storage= 252 cf @ 12.22 hrs
 Average Depth at Peak Storage= 0.0'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 733.8 cfs

40.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 140.00'
 Length= 182.0' Slope= 0.0665 '/'
 Inlet Invert= 681.50', Outlet Invert= 669.40'




Summary for Reach 23R-S: Swale

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.36" for 2-Year event
 Inflow = 1.8 cfs @ 12.08 hrs, Volume= 0.1 af
 Outflow = 1.7 cfs @ 12.14 hrs, Volume= 0.1 af, Atten= 6%, Lag= 4.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.2 fps, Min. Travel Time= 2.1 min
 Avg. Velocity = 0.9 fps, Avg. Travel Time= 5.2 min

Peak Storage= 213 cf @ 12.11 hrs
 Average Depth at Peak Storage= 0.4'
 Bank-Full Depth= 1.0' Flow Area= 3.0 sf, Capacity= 10.5 cfs

1.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 5.00'
 Length= 270.0' Slope= 0.0585 '/'
 Inlet Invert= 705.50', Outlet Invert= 689.70'



Summary for Reach 24R:

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth = 0.79" for 2-Year event
 Inflow = 20.4 cfs @ 12.43 hrs, Volume= 2.9 af
 Outflow = 16.9 cfs @ 12.97 hrs, Volume= 2.9 af, Atten= 17%, Lag= 32.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.0 fps, Min. Travel Time= 18.7 min
 Avg. Velocity = 0.8 fps, Avg. Travel Time= 49.3 min

Peak Storage= 19,078 cf @ 12.66 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,322.5 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass (cultivated farm land)
 Side Slope Z-value= 50.0 ' Top Width= 200.00'
 Length= 2,220.0' Slope= 0.0633 '
 Inlet Invert= 822.00', Outlet Invert= 681.50'




Summary for Reach 24R-G: Crops

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 0.79" for 2-Year event
 Inflow = 13.2 cfs @ 13.69 hrs, Volume= 2.9 af
 Outflow = 12.5 cfs @ 14.07 hrs, Volume= 2.9 af, Atten= 5%, Lag= 23.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.9 fps, Min. Travel Time= 12.5 min
 Avg. Velocity = 0.8 fps, Avg. Travel Time= 28.3 min

Peak Storage= 9,412 cf @ 13.87 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,444.6 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 ' Top Width= 200.00'
 Length= 1,397.0' Slope= 0.0755 '
 Inlet Invert= 787.00', Outlet Invert= 681.50'



Summary for Reach 24R-W: Woods

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 0.79" for 2-Year event
 Inflow = 16.9 cfs @ 12.97 hrs, Volume= 2.9 af
 Outflow = 13.2 cfs @ 13.69 hrs, Volume= 2.9 af, Atten= 22%, Lag= 43.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.3 fps, Min. Travel Time= 24.2 min
 Avg. Velocity = 0.1 fps, Avg. Travel Time= 58.8 min

Peak Storage= 19,209 cf @ 13.29 hrs
 Average Depth at Peak Storage= 0.3'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 91.5 cfs

100.00' x 1.00' deep channel, n= 0.400 Sheet flow: Woods+light brush
 Side Slope Z-value= 50.0 ' / ' Top Width= 200.00'
 Length= 480.0' Slope= 0.0396 ' / '
 Inlet Invert= 806.00', Outlet Invert= 787.00'



Summary for Reach 25RG: Grass

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.25" for 2-Year event
 Inflow = 0.7 cfs @ 12.22 hrs, Volume= 0.1 af
 Outflow = 0.4 cfs @ 12.92 hrs, Volume= 0.1 af, Atten= 46%, Lag= 41.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.6 fps, Min. Travel Time= 23.3 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 29.5 min

Peak Storage= 564 cf @ 12.52 hrs
 Average Depth at Peak Storage= 0.0'
 Bank-Full Depth= 1.0' Flow Area= 100.0 sf, Capacity= 786.7 cfs

50.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 ' / ' Top Width= 150.00'
 Length= 848.0' Slope= 0.0590 ' / '
 Inlet Invert= 725.00', Outlet Invert= 675.00'



Summary for Reach 25RS: Swale

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.25" for 2-Year event
 Inflow = 0.8 cfs @ 12.18 hrs, Volume= 0.1 af
 Outflow = 0.8 cfs @ 12.22 hrs, Volume= 0.1 af, Atten= 1%, Lag= 2.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.1 fps, Min. Travel Time= 1.3 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 3.0 min

Peak Storage= 59 cf @ 12.20 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 1.0' Flow Area= 7.0 sf, Capacity= 22.2 cfs

4.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 3.0 '/' Top Width= 10.00'
 Length= 85.0' Slope= 0.0365 '/'
 Inlet Invert= 733.00', Outlet Invert= 729.90'



Summary for Reach 26R: (new Reach)

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.36" for 2-Year event
 Inflow = 1.7 cfs @ 12.14 hrs, Volume= 0.1 af
 Outflow = 1.6 cfs @ 12.19 hrs, Volume= 0.1 af, Atten= 5%, Lag= 2.8 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.7 fps, Min. Travel Time= 1.5 min
 Avg. Velocity = 0.6 fps, Avg. Travel Time= 4.3 min

Peak Storage= 147 cf @ 12.16 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 2.0' Flow Area= 16.0 sf, Capacity= 92.5 cfs

4.00' x 2.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 12.00'
 Length= 151.0' Slope= 0.0543 '/'
 Inlet Invert= 689.70', Outlet Invert= 681.50'



Summary for Reach 31R: Grass

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 0.79" for 2-Year event
 Inflow = 3.0 cfs @ 12.14 hrs, Volume= 0.2 af
 Outflow = 2.9 cfs @ 12.25 hrs, Volume= 0.2 af, Atten= 5%, Lag= 6.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.2 fps, Min. Travel Time= 3.7 min
 Avg. Velocity = 0.1 fps, Avg. Travel Time= 12.6 min

Peak Storage= 644 cf @ 12.19 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 44.5 cfs

40.00' x 1.00' deep channel, n= 0.100 Heavy timber, flow below branches
 Side Slope Z-value= 50.0 ' ' Top Width= 140.00'
 Length= 50.0' Slope= 0.0020 ' '
 Inlet Invert= 805.50', Outlet Invert= 805.40'



Summary for Reach 40R: Route 30 Ditch

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 1.19" for 2-Year event
 Inflow = 5.6 cfs @ 12.62 hrs, Volume= 0.9 af
 Outflow = 5.6 cfs @ 12.66 hrs, Volume= 0.9 af, Atten= 0%, Lag= 2.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 4.3 fps, Min. Travel Time= 0.6 min
 Avg. Velocity = 1.7 fps, Avg. Travel Time= 1.6 min

Peak Storage= 209 cf @ 12.65 hrs
 Average Depth at Peak Storage= 0.5'
 Bank-Full Depth= 2.0' Flow Area= 12.0 sf, Capacity= 116.0 cfs

2.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 2.0 ' ' Top Width= 10.00'
 Length= 160.0' Slope= 0.0459 ' '
 Inlet Invert= 662.34', Outlet Invert= 655.00'



Summary for Pond 20P: Culvert-2

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 0.76" for 2-Year event
 Inflow = 13.0 cfs @ 14.07 hrs, Volume= 3.2 af
 Outflow = 13.0 cfs @ 14.07 hrs, Volume= 3.2 af, Atten= 0%, Lag= 0.0 min
 Primary = 13.0 cfs @ 14.07 hrs, Volume= 3.2 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 684.26' @ 14.07 hrs Surf.Area= 735 sf Storage= 743 cf

Plug-Flow detention time= 0.9 min calculated for 3.2 af (100% of inflow)
 Center-of-Mass det. time= 0.8 min (1,029.2 - 1,028.4)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 681.00' | 3,164 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 681.00 | 4 | 0 | 0 |
| 682.00 | 67 | 36 | 36 |
| 683.00 | 203 | 135 | 171 |
| 684.00 | 591 | 397 | 568 |
| 685.00 | 1,137 | 864 | 1,432 |
| 686.00 | 2,328 | 1,733 | 3,164 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 681.50' | 12.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 681.50' / 681.00' S= 0.0143 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 684.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=13.0 cfs @ 14.07 hrs HW=684.26' (Free Discharge)
 1=Culvert (Inlet Controls 5.7 cfs @ 7.2 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 7.3 cfs @ 1.4 fps)

Summary for Pond 22P: Culvert-7

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 0.61" for 2-Year event
 Inflow = 3.4 cfs @ 12.25 hrs, Volume= 0.4 af
 Outflow = 3.2 cfs @ 12.31 hrs, Volume= 0.4 af, Atten= 5%, Lag= 3.7 min
 Primary = 3.2 cfs @ 12.31 hrs, Volume= 0.4 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 729.07' @ 12.31 hrs Surf.Area= 1,293 sf Storage= 914 cf

Plug-Flow detention time= 13.0 min calculated for 0.4 af (99% of inflow)
 Center-of-Mass det. time= 9.3 min (905.1 - 895.9)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 728.00' | 6,013 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 728.00 | 457 | 0 | 0 |
| 729.00 | 1,190 | 824 | 824 |
| 730.00 | 2,606 | 1,898 | 2,722 |
| 731.00 | 3,977 | 3,292 | 6,013 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 728.20' | 18.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 728.20' / 727.80' S= 0.0114 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf |
| #2 | Primary | 731.70' | 180.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32 |

Primary OutFlow Max=3.2 cfs @ 12.31 hrs HW=729.07' (Free Discharge)

1=Culvert (Barrel Controls 3.2 cfs @ 4.3 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 23P: Culvert-3

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.36" for 2-Year event
 Inflow = 1.8 cfs @ 12.07 hrs, Volume= 0.1 af
 Outflow = 1.8 cfs @ 12.08 hrs, Volume= 0.1 af, Atten= 1%, Lag= 0.5 min
 Primary = 1.8 cfs @ 12.08 hrs, Volume= 0.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 706.73' @ 12.08 hrs Surf.Area= 93 sf Storage= 42 cf

Plug-Flow detention time= 0.7 min calculated for 0.1 af (100% of inflow)
 Center-of-Mass det. time= 0.6 min (916.9 - 916.3)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 706.00' | 3,590 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 706.00 | 23 | 0 | 0 |
| 707.00 | 120 | 72 | 72 |
| 708.00 | 571 | 346 | 417 |
| 709.00 | 1,324 | 948 | 1,365 |
| 710.00 | 3,126 | 2,225 | 3,590 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 706.00' | 12.0" Round Culvert L= 31.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 706.00' / 704.50' S= 0.0484 ' S= 0.0484 ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 708.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=1.7 cfs @ 12.08 hrs HW=706.71' (Free Discharge)

1=Culvert (Inlet Controls 1.7 cfs @ 2.9 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 24P: Culvert-6

Inflow Area = 5.2 ac, 0.27% Impervious, Inflow Depth = 0.79" for 2-Year event
 Inflow = 3.8 cfs @ 12.19 hrs, Volume= 0.3 af
 Outflow = 3.8 cfs @ 12.19 hrs, Volume= 0.3 af, Atten= 0%, Lag= 0.1 min
 Primary = 3.8 cfs @ 12.19 hrs, Volume= 0.3 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 823.03' @ 12.19 hrs Surf.Area= 559 sf Storage= 14 cf

Plug-Flow detention time= 0.1 min calculated for 0.3 af (100% of inflow)
 Center-of-Mass det. time= 0.1 min (876.8 - 876.7)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 823.00' | 18,148 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 823.00 | 493 | 0 | 0 |
| 824.00 | 3,067 | 1,780 | 1,780 |
| 825.00 | 8,169 | 5,618 | 7,398 |
| 826.00 | 13,330 | 10,750 | 18,148 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 821.00' | 12.0" Round Culvert L= 57.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 821.00' / 820.50' S= 0.0088 ' S= 0.0088 ' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 824.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=4.5 cfs @ 12.19 hrs HW=823.03' (Free Discharge)

1=Culvert (Barrel Controls 4.5 cfs @ 5.7 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 25P: Culvert-4

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.25" for 2-Year event
 Inflow = 0.8 cfs @ 12.18 hrs, Volume= 0.1 af
 Outflow = 0.8 cfs @ 12.18 hrs, Volume= 0.1 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.8 cfs @ 12.18 hrs, Volume= 0.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 734.04' @ 12.18 hrs Surf.Area= 42 sf Storage= 2 cf

Plug-Flow detention time= 0.0 min calculated for 0.1 af (100% of inflow)
 Center-of-Mass det. time= 0.0 min (950.0 - 950.0)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 734.00' | 7,832 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 734.00 | 38 | 0 | 0 |
| 735.00 | 131 | 85 | 85 |
| 736.00 | 417 | 274 | 359 |
| 737.00 | 978 | 698 | 1,056 |
| 738.00 | 1,789 | 1,384 | 2,440 |
| 739.00 | 2,699 | 2,244 | 4,684 |
| 740.00 | 3,598 | 3,149 | 7,832 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 733.50' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 733.50' / 733.00' S= 0.0200 ' / Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 736.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=1.1 cfs @ 12.18 hrs HW=734.04' (Free Discharge)
 1=Culvert (Inlet Controls 1.1 cfs @ 2.5 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 26P: Depression

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.25" for 2-Year event
 Inflow = 0.8 cfs @ 12.22 hrs, Volume= 0.1 af
 Outflow = 0.7 cfs @ 12.22 hrs, Volume= 0.1 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.7 cfs @ 12.22 hrs, Volume= 0.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 722.02' @ 12.22 hrs Surf.Area= 193 sf Storage= 3 cf

Plug-Flow detention time= 0.1 min calculated for 0.1 af (100% of inflow)

Center-of-Mass det. time= 0.1 min (953.9 - 953.8)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 722.00' | 2,084 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 722.00 | 187 | 0 | 0 |
| 723.00 | 515 | 351 | 351 |
| 724.00 | 850 | 683 | 1,034 |
| 725.00 | 1,250 | 1,050 | 2,084 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 722.00' | 100.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64 |

Primary OutFlow Max=0.6 cfs @ 12.22 hrs HW=722.02' (Free Discharge)
 ↑1=**Broad-Crested Rectangular Weir**(Weir Controls 0.6 cfs @ 0.3 fps)

Summary for Pond 31P: Culvert-5

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 0.79" for 2-Year event
 Inflow = 3.1 cfs @ 12.11 hrs, Volume= 0.2 af
 Outflow = 3.0 cfs @ 12.14 hrs, Volume= 0.2 af, Atten= 3%, Lag= 1.9 min
 Primary = 3.0 cfs @ 12.14 hrs, Volume= 0.2 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 807.15' @ 12.14 hrs Surf.Area= 337 sf Storage= 292 cf

Plug-Flow detention time= 3.1 min calculated for 0.2 af (100% of inflow)
 Center-of-Mass det. time= 3.1 min (874.0 - 870.9)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 806.00' | 19,462 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 806.00 | 184 | 0 | 0 |
| 807.00 | 306 | 245 | 245 |
| 808.00 | 517 | 412 | 657 |
| 809.00 | 7,488 | 4,003 | 4,659 |
| 810.00 | 22,117 | 14,803 | 19,462 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 806.00' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 806.00' / 805.70' S= 0.0120 ' / Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 808.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir |

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60
 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=3.0 cfs @ 12.14 hrs HW=807.14' (Free Discharge)

1=Culvert (Inlet Controls 3.0 cfs @ 3.8 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 40P: Culvert-1 [Route 30]

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 1.19" for 2-Year event
 Inflow = 5.6 cfs @ 12.64 hrs, Volume= 0.9 af
 Outflow = 5.6 cfs @ 12.62 hrs, Volume= 0.9 af, Atten= 0%, Lag= 0.0 min
 Primary = 5.6 cfs @ 12.62 hrs, Volume= 0.9 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 665.37' @ 12.62 hrs Surf.Area= 435 sf Storage= 157 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)
 Center-of-Mass det. time= 0.2 min (884.7 - 884.6)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 663.50' | 6,466 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 663.50 | 5 | 0 | 0 |
| 664.00 | 13 | 5 | 5 |
| 665.00 | 94 | 54 | 58 |
| 666.00 | 1,006 | 550 | 608 |
| 667.00 | 2,797 | 1,902 | 2,510 |
| 668.00 | 5,115 | 3,956 | 6,466 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 663.10' | 12.0" Round Culvert L= 95.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 663.10' / 662.30' S= 0.0084 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 665.30' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=5.6 cfs @ 12.62 hrs HW=665.37' (Free Discharge)

1=Culvert (Barrel Controls 4.5 cfs @ 5.7 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 1.0 cfs @ 0.7 fps)

Summary for Link POA 1: SOUTHEAST

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 0.53" for 2-Year event
Inflow = 11.8 cfs @ 12.17 hrs, Volume= 1.1 af
Primary = 11.8 cfs @ 12.17 hrs, Volume= 1.1 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: WEST

Inflow Area = 84.1 ac, 0.04% Impervious, Inflow Depth > 0.77" for 2-Year event
Inflow = 27.5 cfs @ 12.11 hrs, Volume= 5.4 af
Primary = 27.5 cfs @ 12.11 hrs, Volume= 5.4 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: NORTH

Inflow Area = 12.5 ac, 0.00% Impervious, Inflow Depth = 0.76" for 2-Year event
Inflow = 8.7 cfs @ 12.23 hrs, Volume= 0.8 af
Primary = 8.7 cfs @ 12.23 hrs, Volume= 0.8 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA-4: ROUTE 30

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 1.19" for 2-Year event
Inflow = 5.6 cfs @ 12.66 hrs, Volume= 0.9 af
Primary = 5.6 cfs @ 12.66 hrs, Volume= 0.9 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Subcatchment 10:

Runoff = 30.6 cfs @ 12.15 hrs, Volume= 2.5 af, Depth= 1.21"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.1 | 48 | Brush, Good, HSG B |
| 3.1 | 73 | Brush, Good, HSG D |
| 3.7 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.1 | 55 | Woods, Good, HSG B |
| 12.6 | 77 | Woods, Good, HSG D |
| 24.6 | 72 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, |
| | | | | | Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, |
| | | | | | Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 20:

Runoff = 39.8 cfs @ 12.45 hrs, Volume= 5.2 af, Depth= 1.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.8 | 48 | Brush, Good, HSG B |
| 5.1 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.6 | 96 | Gravel surface, HSG D |
| 0.7 | 58 | Meadow, non-grazed, HSG B |
| 9.0 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 5.0 | 78 | Row crops, straight row, Good, HSG B |
| 8.3 | 89 | Row crops, straight row, Good, HSG D |
| 1.0 | 55 | Woods, Good, HSG B |
| 8.3 | 77 | Woods, Good, HSG D |
| 38.9 | 78 | Weighted Average |
| 38.9 | | 99.98% Pervious Area |
| 0.0 | | 0.02% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 30.7 | 50 | 0.0010 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 4.8 | 580 | 0.0840 | 2.0 | | Shallow Concentrated Flow, Solar Area Short Grass Pasture Kv= 7.0 fps |
| 9.7 | 550 | 0.0360 | 0.9 | | Shallow Concentrated Flow, Stumps Remain Woodland Kv= 5.0 fps |
| 45.2 | 1,180 | Total | | | |

Summary for Subcatchment 21:

Runoff = 8.2 cfs @ 12.23 hrs, Volume= 0.8 af, Depth= 1.34"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.3 | 48 | Brush, Good, HSG B |
| 1.0 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 0.7 | 78 | Meadow, non-grazed, HSG D |
| 1.2 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 0.8 | 55 | Woods, Good, HSG B |
| 2.8 | 77 | Woods, Good, HSG D |
| 7.0 | 74 | Weighted Average |
| 7.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 17.6 | 50 | 0.0040 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 1.0 | 71 | 0.0300 | 1.2 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.2 | 474 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 0.5 | 64 | 0.1100 | 2.3 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.0 | 564 | 0.0250 | 2.4 | | Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps |
| 27.3 | 1,223 | Total | | | |

Summary for Subcatchment 22:

Runoff = 52.4 cfs @ 12.10 hrs, Volume= 3.6 af, Depth= 1.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 48 | Brush, Good, HSG B |
| 0.1 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 1.0 | 58 | Meadow, non-grazed, HSG B |
| 8.5 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 10.8 | 89 | Row crops, straight row, Good, HSG D |
| 0.0 | 55 | Woods, Good, HSG B |
| 2.2 | 77 | Woods, Good, HSG D |
| 23.0 | 82 | Weighted Average |
| 23.0 | | 100.00% Pervious Area |
| 0.0 | | 0.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 5.3 | 50 | 0.0800 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 8.1 | 807 | 0.0560 | 1.7 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.8 | 403 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.2 | 1,260 | Total | | | |

Summary for Subcatchment 23:

Runoff = 5.9 cfs @ 12.05 hrs, Volume= 0.4 af, Depth= 0.93"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 96 | Gravel surface, HSG B |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.9 | 58 | Meadow, non-grazed, HSG B |
| 1.3 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.7 | 67 | Weighted Average |
| 4.7 | | 99.80% Pervious Area |
| 0.0 | | 0.20% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 4.9 | 50 | 0.0980 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 3.8 | 402 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.1 | 304 | 0.0130 | 1.6 | 4.9 | Trap/Vee/Rect Channel Flow, Roadside swale Bot.W=1.00' D=1.00' Z= 2.0 '/' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 11.8 | 756 | Total | | | |

Summary for Subcatchment 24:

Runoff = 8.2 cfs @ 12.18 hrs, Volume= 0.7 af, Depth= 1.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|---------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 5.1 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG B |
| 0.0 | 98 | Paved parking, HSG D |
| 5.2 | 78 | Weighted Average |
| 5.2 | | 99.73% Pervious Area |
| 0.0 | | 0.27% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 10.7 | 50 | 0.0140 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 13.1 | 1,227 | 0.0500 | 1.6 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 23.8 | 1,277 | Total | | | |

Summary for Subcatchment 25:

Runoff = 3.7 cfs @ 12.14 hrs, Volume= 0.3 af, Depth= 0.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.7 | 48 | Brush, Good, HSG B |
| 0.7 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.3 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 2.7 | 55 | Woods, Good, HSG B |
| 0.5 | 77 | Woods, Good, HSG D |
| 5.4 | 63 | Weighted Average |
| 5.4 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 11.8 | 50 | 0.0300 | 0.1 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 1.2 | 80 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 4.5 | 500 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 1.0 | 103 | 0.1200 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 18.5 | 733 | Total | | | |

Summary for Subcatchment 30:

Runoff = 12.9 cfs @ 12.20 hrs, Volume= 1.2 af, Depth= 1.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 5.4 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.1 | 89 | Row crops, straight row, Good, HSG D |
| 0.4 | 55 | Woods, Good, HSG B |
| 1.8 | 77 | Woods, Good, HSG D |
| 9.0 | 77 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 8.9 | 50 | 0.0220 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 16.7 | 1,540 | 0.0480 | 1.5 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 25.6 | 1,590 | Total | | | |

Summary for Subcatchment 31:

Runoff = 6.6 cfs @ 12.10 hrs, Volume= 0.5 af, Depth= 1.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.1 | 96 | Gravel surface, HSG D |
| 3.4 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 3.5 | 78 | Weighted Average |
| 3.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 11.4 | 50 | 0.0120 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 6.1 | 396 | 0.0240 | 1.1 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.5 | 446 | Total | | | |

Summary for Subcatchment 40:

Runoff = 10.3 cfs @ 12.63 hrs, Volume= 1.6 af, Depth= 2.14"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 10-Year Rainfall=3.64"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.0 | 78 | Row crops, straight row, Good, HSG B |
| 5.6 | 89 | Row crops, straight row, Good, HSG D |
| 0.3 | 55 | Woods, Good, HSG B |
| 0.8 | 77 | Woods, Good, HSG D |
| 9.0 | 85 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 2.7 | 180 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 10.4 | 1,500 | 0.0710 | 2.4 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 1.0 | 188 | 0.0500 | 3.2 | 9.7 | Trap/Vee/Rect Channel Flow, Roadside Swale Bot.W=1.00' D=1.00' Z= 2.0 '/' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 60.3 | 1,918 | Total | | | |


Summary for Reach 20R-G: Grass

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 1.56" for 10-Year event
 Inflow = 34.2 cfs @ 13.58 hrs, Volume= 6.6 af
 Outflow = 34.1 cfs @ 13.62 hrs, Volume= 6.6 af, Atten= 0%, Lag= 1.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.5 fps, Min. Travel Time= 1.1 min
 Avg. Velocity = 1.1 fps, Avg. Travel Time= 2.7 min

Peak Storage= 2,268 cf @ 13.60 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 2.0' Flow Area= 400.0 sf, Capacity= 5,078.6 cfs

100.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 300.00'
 Length= 169.0' Slope= 0.0609 '/'
 Inlet Invert= 679.00', Outlet Invert= 668.70'



Summary for Reach 20R-S: Swale

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 1.56" for 10-Year event
 Inflow = 34.2 cfs @ 13.57 hrs, Volume= 6.6 af
 Outflow = 34.2 cfs @ 13.58 hrs, Volume= 6.6 af, Atten= 0%, Lag= 0.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.1 fps, Min. Travel Time= 0.3 min
 Avg. Velocity = 1.5 fps, Avg. Travel Time= 0.7 min

Peak Storage= 702 cf @ 13.58 hrs
 Average Depth at Peak Storage= 1.5'
 Bank-Full Depth= 2.0' Flow Area= 18.0 sf, Capacity= 66.5 cfs

3.00' x 2.00' deep channel, n= 0.078 Riprap, 12-inch
 Side Slope Z-value= 3.0 '/' Top Width= 15.00'
 Length= 64.0' Slope= 0.0313 '/'
 Inlet Invert= 681.00', Outlet Invert= 679.00'



Summary for Reach 23R: Crops

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 1.33" for 10-Year event
 Inflow = 7.5 cfs @ 12.31 hrs, Volume= 0.8 af
 Outflow = 6.9 cfs @ 12.56 hrs, Volume= 0.8 af, Atten= 9%, Lag= 15.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.4 fps, Min. Travel Time= 9.1 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 23.2 min

Peak Storage= 3,740 cf @ 12.41 hrs
 Average Depth at Peak Storage= 0.0'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,304.4 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 200.00'
 Length= 752.0' Slope= 0.0616 '/'
 Inlet Invert= 727.80', Outlet Invert= 681.50'



Summary for Reach 23R-G: Grass

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.93" for 10-Year event
 Inflow = 5.1 cfs @ 12.17 hrs, Volume= 0.4 af
 Outflow = 4.9 cfs @ 12.22 hrs, Volume= 0.4 af, Atten= 3%, Lag= 3.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.7 fps, Min. Travel Time= 1.8 min
 Avg. Velocity = 0.6 fps, Avg. Travel Time= 5.2 min

Peak Storage= 531 cf @ 12.19 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 733.8 cfs

40.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 140.00'
 Length= 182.0' Slope= 0.0665 '/'
 Inlet Invert= 681.50', Outlet Invert= 669.40'



Summary for Reach 23R-S: Swale

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.93" for 10-Year event
 Inflow = 5.8 cfs @ 12.10 hrs, Volume= 0.4 af
 Outflow = 5.3 cfs @ 12.14 hrs, Volume= 0.4 af, Atten= 10%, Lag= 2.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.9 fps, Min. Travel Time= 1.5 min
 Avg. Velocity = 1.1 fps, Avg. Travel Time= 4.1 min

Peak Storage= 499 cf @ 12.11 hrs
 Average Depth at Peak Storage= 0.7'
 Bank-Full Depth= 1.0' Flow Area= 3.0 sf, Capacity= 10.5 cfs

1.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 5.00'
 Length= 270.0' Slope= 0.0585 '/'
 Inlet Invert= 705.50', Outlet Invert= 689.70'



Summary for Reach 24R:

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth = 1.60" for 10-Year event
 Inflow = 45.5 cfs @ 12.44 hrs, Volume= 5.9 af
 Outflow = 40.9 cfs @ 12.82 hrs, Volume= 5.9 af, Atten= 10%, Lag= 22.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.8 fps, Min. Travel Time= 13.4 min
 Avg. Velocity = 0.9 fps, Avg. Travel Time= 41.9 min

Peak Storage= 33,108 cf @ 12.59 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,322.5 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass (cultivated farm land)
 Side Slope Z-value= 50.0 ' ' Top Width= 200.00'
 Length= 2,220.0' Slope= 0.0633 ' '
 Inlet Invert= 822.00', Outlet Invert= 681.50'



Summary for Reach 24R-G: Crops

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 1.60" for 10-Year event
 Inflow = 34.1 cfs @ 13.32 hrs, Volume= 5.9 af
 Outflow = 32.9 cfs @ 13.57 hrs, Volume= 5.9 af, Atten= 4%, Lag= 15.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.7 fps, Min. Travel Time= 8.7 min
 Avg. Velocity = 1.0 fps, Avg. Travel Time= 24.0 min

Peak Storage= 17,155 cf @ 13.43 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,444.6 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 ' ' Top Width= 200.00'
 Length= 1,397.0' Slope= 0.0755 ' '
 Inlet Invert= 787.00', Outlet Invert= 681.50'



Summary for Reach 24R-W: Woods

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 1.60" for 10-Year event
 Inflow = 40.9 cfs @ 12.82 hrs, Volume= 5.9 af
 Outflow = 34.1 cfs @ 13.32 hrs, Volume= 5.9 af, Atten= 17%, Lag= 30.2 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.5 fps, Min. Travel Time= 17.7 min
 Avg. Velocity = 0.2 fps, Avg. Travel Time= 50.2 min

Peak Storage= 36,309 cf @ 13.02 hrs
 Average Depth at Peak Storage= 0.6'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 91.5 cfs

100.00' x 1.00' deep channel, n= 0.400 Sheet flow: Woods+light brush
 Side Slope Z-value= 50.0 '/' Top Width= 200.00'
 Length= 480.0' Slope= 0.0396 '/'
 Inlet Invert= 806.00', Outlet Invert= 787.00'



Summary for Reach 25RG: Grass

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.73" for 10-Year event
 Inflow = 3.6 cfs @ 12.18 hrs, Volume= 0.3 af
 Outflow = 2.7 cfs @ 12.50 hrs, Volume= 0.3 af, Atten= 26%, Lag= 19.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.2 fps, Min. Travel Time= 11.6 min
 Avg. Velocity = 0.5 fps, Avg. Travel Time= 27.1 min

Peak Storage= 1,860 cf @ 12.30 hrs
 Average Depth at Peak Storage= 0.0'
 Bank-Full Depth= 1.0' Flow Area= 100.0 sf, Capacity= 786.7 cfs

50.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 150.00'
 Length= 848.0' Slope= 0.0590 '/'
 Inlet Invert= 725.00', Outlet Invert= 675.00'



Summary for Reach 25RS: Swale

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.73" for 10-Year event
 Inflow = 3.7 cfs @ 12.16 hrs, Volume= 0.3 af
 Outflow = 3.6 cfs @ 12.18 hrs, Volume= 0.3 af, Atten= 2%, Lag= 1.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 1.9 fps, Min. Travel Time= 0.8 min
 Avg. Velocity = 0.7 fps, Avg. Travel Time= 2.1 min

Peak Storage= 167 cf @ 12.17 hrs
 Average Depth at Peak Storage= 0.4'
 Bank-Full Depth= 1.0' Flow Area= 7.0 sf, Capacity= 22.2 cfs

4.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 3.0 '/' Top Width= 10.00'
 Length= 85.0' Slope= 0.0365 '/'
 Inlet Invert= 733.00', Outlet Invert= 729.90'




Summary for Reach 26R: (new Reach)

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.93" for 10-Year event
 Inflow = 5.3 cfs @ 12.14 hrs, Volume= 0.4 af
 Outflow = 5.1 cfs @ 12.17 hrs, Volume= 0.4 af, Atten= 3%, Lag= 1.6 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.5 fps, Min. Travel Time= 1.0 min
 Avg. Velocity = 0.8 fps, Avg. Travel Time= 3.3 min

Peak Storage= 315 cf @ 12.15 hrs
 Average Depth at Peak Storage= 0.4'
 Bank-Full Depth= 2.0' Flow Area= 16.0 sf, Capacity= 92.5 cfs

4.00' x 2.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 12.00'
 Length= 151.0' Slope= 0.0543 '/'
 Inlet Invert= 689.70', Outlet Invert= 681.50'



Summary for Reach 31R: Grass

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 1.60" for 10-Year event
 Inflow = 5.2 cfs @ 12.20 hrs, Volume= 0.5 af
 Outflow = 5.1 cfs @ 12.29 hrs, Volume= 0.5 af, Atten= 1%, Lag= 5.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.3 fps, Min. Travel Time= 3.1 min
 Avg. Velocity = 0.1 fps, Avg. Travel Time= 10.6 min

Peak Storage= 951 cf @ 12.24 hrs
 Average Depth at Peak Storage= 0.3'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 44.5 cfs

40.00' x 1.00' deep channel, n= 0.100 Heavy timber, flow below branches
 Side Slope Z-value= 50.0 ' ' Top Width= 140.00'
 Length= 50.0' Slope= 0.0020 ' '
 Inlet Invert= 805.50', Outlet Invert= 805.40'



Summary for Reach 40R: Route 30 Ditch

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 2.14" for 10-Year event
 Inflow = 10.3 cfs @ 12.63 hrs, Volume= 1.6 af
 Outflow = 10.3 cfs @ 12.65 hrs, Volume= 1.6 af, Atten= 0%, Lag= 0.9 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 5.1 fps, Min. Travel Time= 0.5 min
 Avg. Velocity = 1.9 fps, Avg. Travel Time= 1.4 min

Peak Storage= 321 cf @ 12.64 hrs
 Average Depth at Peak Storage= 0.6'
 Bank-Full Depth= 2.0' Flow Area= 12.0 sf, Capacity= 116.0 cfs

2.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 2.0 ' ' Top Width= 10.00'
 Length= 160.0' Slope= 0.0459 ' '
 Inlet Invert= 662.34', Outlet Invert= 655.00'



Summary for Pond 20P: Culvert-2

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 1.56" for 10-Year event
 Inflow = 34.2 cfs @ 13.57 hrs, Volume= 6.6 af
 Outflow = 34.2 cfs @ 13.57 hrs, Volume= 6.6 af, Atten= 0%, Lag= 0.2 min
 Primary = 34.2 cfs @ 13.57 hrs, Volume= 6.6 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 684.65' @ 13.57 hrs Surf.Area= 945 sf Storage= 1,066 cf

Plug-Flow detention time= 0.8 min calculated for 6.6 af (100% of inflow)
 Center-of-Mass det. time= 0.8 min (973.8 - 973.0)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 681.00' | 3,164 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 681.00 | 4 | 0 | 0 |
| 682.00 | 67 | 36 | 36 |
| 683.00 | 203 | 135 | 171 |
| 684.00 | 591 | 397 | 568 |
| 685.00 | 1,137 | 864 | 1,432 |
| 686.00 | 2,328 | 1,733 | 3,164 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 681.50' | 12.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 681.50' / 681.00' S= 0.0143 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 684.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=34.1 cfs @ 13.57 hrs HW=684.65' (Free Discharge)
 1=Culvert (Inlet Controls 6.2 cfs @ 7.8 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 28.0 cfs @ 2.2 fps)

Summary for Pond 22P: Culvert-7

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 1.34" for 10-Year event
 Inflow = 8.2 cfs @ 12.23 hrs, Volume= 0.8 af
 Outflow = 7.5 cfs @ 12.31 hrs, Volume= 0.8 af, Atten= 8%, Lag= 5.0 min
 Primary = 7.5 cfs @ 12.31 hrs, Volume= 0.8 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 729.75' @ 12.31 hrs Surf.Area= 2,248 sf Storage= 2,108 cf

Plug-Flow detention time= 9.0 min calculated for 0.8 af (100% of inflow)
 Center-of-Mass det. time= 6.9 min (877.5 - 870.7)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 728.00' | 6,013 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 728.00 | 457 | 0 | 0 |
| 729.00 | 1,190 | 824 | 824 |
| 730.00 | 2,606 | 1,898 | 2,722 |
| 731.00 | 3,977 | 3,292 | 6,013 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 728.20' | 18.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 728.20' / 727.80' S= 0.0114 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf |
| #2 | Primary | 731.70' | 180.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32 |

Primary OutFlow Max=7.5 cfs @ 12.31 hrs HW=729.74' (Free Discharge)

1=Culvert (Barrel Controls 7.5 cfs @ 5.1 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 23P: Culvert-3

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 0.93" for 10-Year event
 Inflow = 5.9 cfs @ 12.05 hrs, Volume= 0.4 af
 Outflow = 5.8 cfs @ 12.10 hrs, Volume= 0.4 af, Atten= 0%, Lag= 2.7 min
 Primary = 5.8 cfs @ 12.10 hrs, Volume= 0.4 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 708.08' @ 12.09 hrs Surf.Area= 634 sf Storage= 468 cf

Plug-Flow detention time= 0.7 min calculated for 0.4 af (100% of inflow)
 Center-of-Mass det. time= 0.7 min (879.5 - 878.8)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 706.00' | 3,590 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 706.00 | 23 | 0 | 0 |
| 707.00 | 120 | 72 | 72 |
| 708.00 | 571 | 346 | 417 |
| 709.00 | 1,324 | 948 | 1,365 |
| 710.00 | 3,126 | 2,225 | 3,590 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 706.00' | 12.0" Round Culvert L= 31.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 706.00' / 704.50' S= 0.0484 ' S= 0.0484 ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 708.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=5.7 cfs @ 12.10 hrs HW=708.07' (Free Discharge)

↑ **1=Culvert** (Inlet Controls 4.7 cfs @ 6.0 fps)

↓ **2=Broad-Crested Rectangular Weir** (Weir Controls 1.0 cfs @ 0.7 fps)

Summary for Pond 24P: Culvert-6

Inflow Area = 5.2 ac, 0.27% Impervious, Inflow Depth = 1.60" for 10-Year event
 Inflow = 8.2 cfs @ 12.18 hrs, Volume= 0.7 af
 Outflow = 6.4 cfs @ 12.31 hrs, Volume= 0.7 af, Atten= 21%, Lag= 8.1 min
 Primary = 6.4 cfs @ 12.31 hrs, Volume= 0.7 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 824.05' @ 12.32 hrs Surf.Area= 3,340 sf Storage= 1,951 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)
 Center-of-Mass det. time= 1.4 min (857.0 - 855.6)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 823.00' | 18,148 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 823.00 | 493 | 0 | 0 |
| 824.00 | 3,067 | 1,780 | 1,780 |
| 825.00 | 8,169 | 5,618 | 7,398 |
| 826.00 | 13,330 | 10,750 | 18,148 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 821.00' | 12.0" Round Culvert L= 57.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 821.00' / 820.50' S= 0.0088 ' S= 0.0088 ' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 824.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=6.3 cfs @ 12.31 hrs HW=824.05' (Free Discharge)

↑ **1=Culvert** (Barrel Controls 5.8 cfs @ 7.4 fps)

↓ **2=Broad-Crested Rectangular Weir** (Weir Controls 0.5 cfs @ 0.6 fps)

Summary for Pond 25P: Culvert-4

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.73" for 10-Year event
 Inflow = 3.7 cfs @ 12.14 hrs, Volume= 0.3 af
 Outflow = 3.7 cfs @ 12.16 hrs, Volume= 0.3 af, Atten= 2%, Lag= 0.9 min
 Primary = 3.7 cfs @ 12.16 hrs, Volume= 0.3 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 734.94' @ 12.16 hrs Surf.Area= 125 sf Storage= 77 cf

Plug-Flow detention time= 0.3 min calculated for 0.3 af (100% of inflow)
 Center-of-Mass det. time= 0.2 min (900.5 - 900.3)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 734.00' | 7,832 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 734.00 | 38 | 0 | 0 |
| 735.00 | 131 | 85 | 85 |
| 736.00 | 417 | 274 | 359 |
| 737.00 | 978 | 698 | 1,056 |
| 738.00 | 1,789 | 1,384 | 2,440 |
| 739.00 | 2,699 | 2,244 | 4,684 |
| 740.00 | 3,598 | 3,149 | 7,832 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 733.50' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 733.50' / 733.00' S= 0.0200 ' / Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 736.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=3.6 cfs @ 12.16 hrs HW=734.93' (Free Discharge)

1=Culvert (Inlet Controls 3.6 cfs @ 4.6 fps)
 2=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Summary for Pond 26P: Depression

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 0.73" for 10-Year event
 Inflow = 3.6 cfs @ 12.18 hrs, Volume= 0.3 af
 Outflow = 3.6 cfs @ 12.18 hrs, Volume= 0.3 af, Atten= 0%, Lag= 0.0 min
 Primary = 3.6 cfs @ 12.18 hrs, Volume= 0.3 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 722.06' @ 12.18 hrs Surf.Area= 206 sf Storage= 12 cf

Plug-Flow detention time= 0.1 min calculated for 0.3 af (100% of inflow)

Center-of-Mass det. time= 0.1 min (902.9 - 902.8)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 722.00' | 2,084 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 722.00 | 187 | 0 | 0 |
| 723.00 | 515 | 351 | 351 |
| 724.00 | 850 | 683 | 1,034 |
| 725.00 | 1,250 | 1,050 | 2,084 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 722.00' | 100.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64 |

Primary OutFlow Max=3.5 cfs @ 12.18 hrs HW=722.06' (Free Discharge)
 ↑1=**Broad-Crested Rectangular Weir**(Weir Controls 3.5 cfs @ 0.6 fps)

Summary for Pond 31P: Culvert-5

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 1.60" for 10-Year event
 Inflow = 6.6 cfs @ 12.10 hrs, Volume= 0.5 af
 Outflow = 5.2 cfs @ 12.20 hrs, Volume= 0.5 af, Atten= 22%, Lag= 5.9 min
 Primary = 5.2 cfs @ 12.20 hrs, Volume= 0.5 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 808.36' @ 12.20 hrs Surf.Area= 3,015 sf Storage= 1,289 cf

Plug-Flow detention time= 3.0 min calculated for 0.5 af (100% of inflow)
 Center-of-Mass det. time= 3.0 min (852.8 - 849.7)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 806.00' | 19,462 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 806.00 | 184 | 0 | 0 |
| 807.00 | 306 | 245 | 245 |
| 808.00 | 517 | 412 | 657 |
| 809.00 | 7,488 | 4,003 | 4,659 |
| 810.00 | 22,117 | 14,803 | 19,462 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 806.00' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 806.00' / 805.70' S= 0.0120 ' / Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 808.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir |

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60
 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=5.2 cfs @ 12.20 hrs HW=808.36' (Free Discharge)

↑ **1=Culvert** (Inlet Controls 5.2 cfs @ 6.6 fps)
 ↓ **2=Broad-Crested Rectangular Weir** (Controls 0.0 cfs)

Summary for Pond 40P: Culvert-1 [Route 30]

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 2.14" for 10-Year event
 Inflow = 10.3 cfs @ 12.63 hrs, Volume= 1.6 af
 Outflow = 10.3 cfs @ 12.63 hrs, Volume= 1.6 af, Atten= 0%, Lag= 0.0 min
 Primary = 10.3 cfs @ 12.63 hrs, Volume= 1.6 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 665.52' @ 12.63 hrs Surf.Area= 569 sf Storage= 231 cf

Plug-Flow detention time= 0.2 min calculated for 1.6 af (100% of inflow)
 Center-of-Mass det. time= 0.2 min (867.9 - 867.7)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 663.50' | 6,466 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 663.50 | 5 | 0 | 0 |
| 664.00 | 13 | 5 | 5 |
| 665.00 | 94 | 54 | 58 |
| 666.00 | 1,006 | 550 | 608 |
| 667.00 | 2,797 | 1,902 | 2,510 |
| 668.00 | 5,115 | 3,956 | 6,466 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 663.10' | 12.0" Round Culvert L= 95.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 663.10' / 662.30' S= 0.0084 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 665.30' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=10.2 cfs @ 12.63 hrs HW=665.52' (Free Discharge)

↑ **1=Culvert** (Barrel Controls 4.7 cfs @ 5.9 fps)
 ↓ **2=Broad-Crested Rectangular Weir** (Weir Controls 5.6 cfs @ 1.3 fps)

Summary for Link POA 1: SOUTHEAST

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 1.21" for 10-Year event
Inflow = 30.6 cfs @ 12.15 hrs, Volume= 2.5 af
Primary = 30.6 cfs @ 12.15 hrs, Volume= 2.5 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: WEST

Inflow Area = 84.1 ac, 0.04% Impervious, Inflow Depth > 1.56" for 10-Year event
Inflow = 56.0 cfs @ 12.11 hrs, Volume= 11.0 af
Primary = 56.0 cfs @ 12.11 hrs, Volume= 11.0 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: NORTH

Inflow Area = 12.5 ac, 0.00% Impervious, Inflow Depth = 1.55" for 10-Year event
Inflow = 17.9 cfs @ 12.21 hrs, Volume= 1.6 af
Primary = 17.9 cfs @ 12.21 hrs, Volume= 1.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA-4: ROUTE 30

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 2.14" for 10-Year event
Inflow = 10.3 cfs @ 12.65 hrs, Volume= 1.6 af
Primary = 10.3 cfs @ 12.65 hrs, Volume= 1.6 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Subcatchment 10:

Runoff = 83.8 cfs @ 12.14 hrs, Volume= 6.5 af, Depth= 3.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.1 | 48 | Brush, Good, HSG B |
| 3.1 | 73 | Brush, Good, HSG D |
| 3.7 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.1 | 55 | Woods, Good, HSG B |
| 12.6 | 77 | Woods, Good, HSG D |
| 24.6 | 72 | Weighted Average |
| 24.6 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 6.3 | 50 | 0.0260 | 0.1 | | Sheet Flow, |
| | | | | | Cultivated: Residue>20% n= 0.170 P2= 2.51" |
| 14.6 | 1,456 | 0.0340 | 1.7 | | Shallow Concentrated Flow, |
| | | | | | Cultivated Straight Rows Kv= 9.0 fps |
| 20.9 | 1,506 | Total | | | |

Summary for Subcatchment 20:

Runoff = 96.0 cfs @ 12.42 hrs, Volume= 12.2 af, Depth= 3.77"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.8 | 48 | Brush, Good, HSG B |
| 5.1 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.6 | 96 | Gravel surface, HSG D |
| 0.7 | 58 | Meadow, non-grazed, HSG B |
| 9.0 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 5.0 | 78 | Row crops, straight row, Good, HSG B |
| 8.3 | 89 | Row crops, straight row, Good, HSG D |
| 1.0 | 55 | Woods, Good, HSG B |
| 8.3 | 77 | Woods, Good, HSG D |
| 38.9 | 78 | Weighted Average |
| 38.9 | | 99.98% Pervious Area |
| 0.0 | | 0.02% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|---|
| 30.7 | 50 | 0.0010 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 4.8 | 580 | 0.0840 | 2.0 | | Shallow Concentrated Flow, Solar Area Short Grass Pasture Kv= 7.0 fps |
| 9.7 | 550 | 0.0360 | 0.9 | | Shallow Concentrated Flow, Stumps Remain Woodland Kv= 5.0 fps |
| 45.2 | 1,180 | Total | | | |

Summary for Subcatchment 21:

Runoff = 21.5 cfs @ 12.21 hrs, Volume= 1.9 af, Depth= 3.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.3 | 48 | Brush, Good, HSG B |
| 1.0 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 0.7 | 78 | Meadow, non-grazed, HSG D |
| 1.2 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 0.8 | 55 | Woods, Good, HSG B |
| 2.8 | 77 | Woods, Good, HSG D |
| 7.0 | 74 | Weighted Average |
| 7.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 17.6 | 50 | 0.0040 | 0.0 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 1.0 | 71 | 0.0300 | 1.2 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.2 | 474 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 0.5 | 64 | 0.1100 | 2.3 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 4.0 | 564 | 0.0250 | 2.4 | | Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps |
| 27.3 | 1,223 | Total | | | |

Summary for Subcatchment 22:

Runoff = 114.0 cfs @ 12.09 hrs, Volume= 8.0 af, Depth= 4.18"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 48 | Brush, Good, HSG B |
| 0.1 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 1.0 | 58 | Meadow, non-grazed, HSG B |
| 8.5 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 10.8 | 89 | Row crops, straight row, Good, HSG D |
| 0.0 | 55 | Woods, Good, HSG B |
| 2.2 | 77 | Woods, Good, HSG D |
| 23.0 | 82 | Weighted Average |
| 23.0 | | 100.00% Pervious Area |
| 0.0 | | 0.00% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 5.3 | 50 | 0.0800 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 8.1 | 807 | 0.0560 | 1.7 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.8 | 403 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.2 | 1,260 | Total | | | |

Summary for Subcatchment 23:

Runoff = 18.2 cfs @ 12.04 hrs, Volume= 1.1 af, Depth= 2.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 96 | Gravel surface, HSG B |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.9 | 58 | Meadow, non-grazed, HSG B |
| 1.3 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 4.7 | 67 | Weighted Average |
| 4.7 | | 99.80% Pervious Area |
| 0.0 | | 0.20% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 4.9 | 50 | 0.0980 | 0.2 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 3.8 | 402 | 0.0640 | 1.8 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 3.1 | 304 | 0.0130 | 1.6 | 4.9 | Trap/Vee/Rect Channel Flow, Roadside swale Bot.W=1.00' D=1.00' Z= 2.0 '/' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 11.8 | 756 | Total | | | |

Summary for Subcatchment 24:

Runoff = 19.5 cfs @ 12.17 hrs, Volume= 1.6 af, Depth= 3.77"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|---------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.0 | 58 | Meadow, non-grazed, HSG B |
| 5.1 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 98 | Paved parking, HSG B |
| 0.0 | 98 | Paved parking, HSG D |
| 5.2 | 78 | Weighted Average |
| 5.2 | | 99.73% Pervious Area |
| 0.0 | | 0.27% Impervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 10.7 | 50 | 0.0140 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 13.1 | 1,227 | 0.0500 | 1.6 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 23.8 | 1,277 | Total | | | |

Summary for Subcatchment 25:

Runoff = 14.1 cfs @ 12.12 hrs, Volume= 1.0 af, Depth= 2.32"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.7 | 48 | Brush, Good, HSG B |
| 0.7 | 73 | Brush, Good, HSG D |
| 0.3 | 96 | Gravel surface, HSG B |
| 0.1 | 96 | Gravel surface, HSG D |
| 0.3 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 2.7 | 55 | Woods, Good, HSG B |
| 0.5 | 77 | Woods, Good, HSG D |
| 5.4 | 63 | Weighted Average |
| 5.4 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|----------|---------------|---------------|-------------------|----------------|--|
| 11.8 | 50 | 0.0300 | 0.1 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 1.2 | 80 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 4.5 | 500 | 0.1400 | 1.9 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 1.0 | 103 | 0.1200 | 1.7 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 18.5 | 733 | Total | | | |

Summary for Subcatchment 30:

Runoff = 31.5 cfs @ 12.19 hrs, Volume= 2.7 af, Depth= 3.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 1.0 | 73 | Brush, Good, HSG D |
| 0.0 | 96 | Gravel surface, HSG B |
| 0.2 | 96 | Gravel surface, HSG D |
| 5.4 | 78 | Meadow, non-grazed, HSG D |
| 0.1 | 78 | Row crops, straight row, Good, HSG B |
| 0.1 | 89 | Row crops, straight row, Good, HSG D |
| 0.4 | 55 | Woods, Good, HSG B |
| 1.8 | 77 | Woods, Good, HSG D |
| 9.0 | 77 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 8.9 | 50 | 0.0220 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 16.7 | 1,540 | 0.0480 | 1.5 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 25.6 | 1,590 | Total | | | |

Summary for Subcatchment 31:

Runoff = 15.6 cfs @ 12.10 hrs, Volume= 1.1 af, Depth= 3.77"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.0 | 73 | Brush, Good, HSG D |
| 0.1 | 96 | Gravel surface, HSG D |
| 3.4 | 78 | Meadow, non-grazed, HSG D |
| 0.0 | 89 | Row crops, straight row, Good, HSG D |
| 3.5 | 78 | Weighted Average |
| 3.5 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 11.4 | 50 | 0.0120 | 0.1 | | Sheet Flow, Grass: Dense n= 0.240 P2= 2.51" |
| 6.1 | 396 | 0.0240 | 1.1 | | Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps |
| 17.5 | 446 | Total | | | |

Summary for Subcatchment 40:

Runoff = 21.5 cfs @ 12.62 hrs, Volume= 3.4 af, Depth= 4.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Type II 24-hr 100-Year Rainfall=6.21"

| Area (ac) | CN | Description |
|-----------|----|--------------------------------------|
| 0.1 | 89 | Dirt roads, HSG D |
| 0.3 | 96 | Gravel surface, HSG D |
| 2.0 | 78 | Row crops, straight row, Good, HSG B |
| 5.6 | 89 | Row crops, straight row, Good, HSG D |
| 0.3 | 55 | Woods, Good, HSG B |
| 0.8 | 77 | Woods, Good, HSG D |
| 9.0 | 85 | Weighted Average |
| 9.0 | | 100.00% Pervious Area |

| Tc (min) | Length (feet) | Slope (ft/ft) | Velocity (ft/sec) | Capacity (cfs) | Description |
|-------------|------------------|------------------|----------------------|-------------------|--|
| 46.2 | 50 | 0.0010 | 0.0 | | Sheet Flow, Woods: Light underbrush n= 0.400 P2= 2.51" |
| 2.7 | 180 | 0.0500 | 1.1 | | Shallow Concentrated Flow, Woodland Kv= 5.0 fps |
| 10.4 | 1,500 | 0.0710 | 2.4 | | Shallow Concentrated Flow, Cultivated Straight Rows Kv= 9.0 fps |
| 1.0 | 188 | 0.0500 | 3.2 | 9.7 | Trap/Vee/Rect Channel Flow, Roadside Swale Bot.W=1.00' D=1.00' Z= 2.0 '/' Top.W=5.00' n= 0.069 Riprap, 6-inch |
| 60.3 | 1,918 | Total | | | |

Summary for Reach 20R-G: Grass

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 3.73" for 100-Year event
 Inflow = 92.8 cfs @ 13.24 hrs, Volume= 15.8 af
 Outflow = 92.7 cfs @ 13.26 hrs, Volume= 15.8 af, Atten= 0%, Lag= 1.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.7 fps, Min. Travel Time= 0.8 min
 Avg. Velocity = 1.3 fps, Avg. Travel Time= 2.2 min

Peak Storage= 4,282 cf @ 13.25 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 2.0' Flow Area= 400.0 sf, Capacity= 5,078.6 cfs

100.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 300.00'
 Length= 169.0' Slope= 0.0609 '/'
 Inlet Invert= 679.00', Outlet Invert= 668.70'



Summary for Reach 20R-S: Swale

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 3.73" for 100-Year event
 Inflow = 92.9 cfs @ 13.23 hrs, Volume= 15.8 af
 Outflow = 92.8 cfs @ 13.24 hrs, Volume= 15.8 af, Atten= 0%, Lag= 0.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 4.0 fps, Min. Travel Time= 0.3 min
 Avg. Velocity = 1.7 fps, Avg. Travel Time= 0.6 min

Peak Storage= 1,493 cf @ 13.23 hrs
 Average Depth at Peak Storage= 2.4'
 Bank-Full Depth= 2.0' Flow Area= 18.0 sf, Capacity= 66.5 cfs

3.00' x 2.00' deep channel, n= 0.078 Riprap, 12-inch
 Side Slope Z-value= 3.0 '/' Top Width= 15.00'
 Length= 64.0' Slope= 0.0313 '/'
 Inlet Invert= 681.00', Outlet Invert= 679.00'



Summary for Reach 23R: Crops

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 3.56" for 100-Year event
 Inflow = 29.8 cfs @ 12.22 hrs, Volume= 2.1 af
 Outflow = 24.9 cfs @ 12.42 hrs, Volume= 2.1 af, Atten= 16%, Lag= 11.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.3 fps, Min. Travel Time= 5.5 min
 Avg. Velocity = 0.6 fps, Avg. Travel Time= 20.3 min

Peak Storage= 8,310 cf @ 12.33 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,304.4 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 200.00'
 Length= 752.0' Slope= 0.0616 '/'
 Inlet Invert= 727.80', Outlet Invert= 681.50'



Summary for Reach 23R-G: Grass

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 2.69" for 100-Year event
 Inflow = 17.1 cfs @ 12.10 hrs, Volume= 1.1 af
 Outflow = 16.5 cfs @ 12.13 hrs, Volume= 1.1 af, Atten= 3%, Lag= 2.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.6 fps, Min. Travel Time= 1.1 min
 Avg. Velocity = 0.7 fps, Avg. Travel Time= 4.2 min

Peak Storage= 1,163 cf @ 12.11 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 733.8 cfs

40.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 '/' Top Width= 140.00'
 Length= 182.0' Slope= 0.0665 '/'
 Inlet Invert= 681.50', Outlet Invert= 669.40'




Summary for Reach 23R-S: Swale

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 2.69" for 100-Year event
 Inflow = 18.2 cfs @ 12.05 hrs, Volume= 1.1 af
 Outflow = 17.4 cfs @ 12.08 hrs, Volume= 1.1 af, Atten= 5%, Lag= 2.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.9 fps, Min. Travel Time= 1.2 min
 Avg. Velocity = 1.4 fps, Avg. Travel Time= 3.3 min

Peak Storage= 1,239 cf @ 12.06 hrs
 Average Depth at Peak Storage= 1.3'
 Bank-Full Depth= 1.0' Flow Area= 3.0 sf, Capacity= 10.5 cfs

1.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 5.00'
 Length= 270.0' Slope= 0.0585 '/'
 Inlet Invert= 705.50', Outlet Invert= 689.70'



Summary for Reach 24R:

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth = 3.77" for 100-Year event
 Inflow = 107.4 cfs @ 12.39 hrs, Volume= 13.8 af
 Outflow = 100.9 cfs @ 12.67 hrs, Volume= 13.8 af, Atten= 6%, Lag= 17.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.8 fps, Min. Travel Time= 9.7 min
 Avg. Velocity = 1.1 fps, Avg. Travel Time= 33.8 min

Peak Storage= 58,739 cf @ 12.51 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,322.5 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass (cultivated farm land)
 Side Slope Z-value= 50.0 ' ' Top Width= 200.00'
 Length= 2,220.0' Slope= 0.0633 ' '
 Inlet Invert= 822.00', Outlet Invert= 681.50'



Summary for Reach 24R-G: Crops

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 3.76" for 100-Year event
 Inflow = 90.4 cfs @ 13.06 hrs, Volume= 13.8 af
 Outflow = 88.8 cfs @ 13.24 hrs, Volume= 13.8 af, Atten= 2%, Lag= 10.4 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.9 fps, Min. Travel Time= 6.0 min
 Avg. Velocity = 1.2 fps, Avg. Travel Time= 19.5 min

Peak Storage= 32,130 cf @ 13.14 hrs
 Average Depth at Peak Storage= 0.2'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 1,444.6 cfs

100.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 ' ' Top Width= 200.00'
 Length= 1,397.0' Slope= 0.0755 ' '
 Inlet Invert= 787.00', Outlet Invert= 681.50'



Summary for Reach 24R-W: Woods

Inflow Area = 44.0 ac, 0.05% Impervious, Inflow Depth > 3.76" for 100-Year event
 Inflow = 100.9 cfs @ 12.67 hrs, Volume= 13.8 af
 Outflow = 90.4 cfs @ 13.06 hrs, Volume= 13.8 af, Atten= 10%, Lag= 23.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.6 fps, Min. Travel Time= 13.2 min
 Avg. Velocity = 0.2 fps, Avg. Travel Time= 40.7 min

Peak Storage= 71,470 cf @ 12.84 hrs
 Average Depth at Peak Storage= 1.0'
 Bank-Full Depth= 1.0' Flow Area= 150.0 sf, Capacity= 91.5 cfs

100.00' x 1.00' deep channel, n= 0.400 Sheet flow: Woods+light brush
 Side Slope Z-value= 50.0 ' Top Width= 200.00'
 Length= 480.0' Slope= 0.0396 '
 Inlet Invert= 806.00', Outlet Invert= 787.00'



Summary for Reach 25RG: Grass

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 2.32" for 100-Year event
 Inflow = 13.7 cfs @ 12.14 hrs, Volume= 1.0 af
 Outflow = 12.0 cfs @ 12.33 hrs, Volume= 1.0 af, Atten= 13%, Lag= 11.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.1 fps, Min. Travel Time= 6.6 min
 Avg. Velocity = 0.6 fps, Avg. Travel Time= 21.9 min

Peak Storage= 4,815 cf @ 12.22 hrs
 Average Depth at Peak Storage= 0.1'
 Bank-Full Depth= 1.0' Flow Area= 100.0 sf, Capacity= 786.7 cfs

50.00' x 1.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 50.0 ' Top Width= 150.00'
 Length= 848.0' Slope= 0.0590 '
 Inlet Invert= 725.00', Outlet Invert= 675.00'



Summary for Reach 25RS: Swale

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 2.32" for 100-Year event
 Inflow = 14.0 cfs @ 12.12 hrs, Volume= 1.0 af
 Outflow = 13.7 cfs @ 12.14 hrs, Volume= 1.0 af, Atten= 2%, Lag= 0.7 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 2.8 fps, Min. Travel Time= 0.5 min
 Avg. Velocity = 0.9 fps, Avg. Travel Time= 1.6 min

Peak Storage= 432 cf @ 12.12 hrs
 Average Depth at Peak Storage= 0.8'
 Bank-Full Depth= 1.0' Flow Area= 7.0 sf, Capacity= 22.2 cfs

4.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 3.0 '/' Top Width= 10.00'
 Length= 85.0' Slope= 0.0365 '/'
 Inlet Invert= 733.00', Outlet Invert= 729.90'



Summary for Reach 26R: (new Reach)

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 2.69" for 100-Year event
 Inflow = 17.4 cfs @ 12.08 hrs, Volume= 1.1 af
 Outflow = 17.1 cfs @ 12.10 hrs, Volume= 1.1 af, Atten= 2%, Lag= 1.1 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 3.6 fps, Min. Travel Time= 0.7 min
 Avg. Velocity = 1.0 fps, Avg. Travel Time= 2.5 min

Peak Storage= 722 cf @ 12.09 hrs
 Average Depth at Peak Storage= 0.8'
 Bank-Full Depth= 2.0' Flow Area= 16.0 sf, Capacity= 92.5 cfs

4.00' x 2.00' deep channel, n= 0.069 Riprap, 6-inch
 Side Slope Z-value= 2.0 '/' Top Width= 12.00'
 Length= 151.0' Slope= 0.0543 '/'
 Inlet Invert= 689.70', Outlet Invert= 681.50'



Summary for Reach 31R: Grass

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 3.77" for 100-Year event
 Inflow = 15.0 cfs @ 12.14 hrs, Volume= 1.1 af
 Outflow = 14.5 cfs @ 12.21 hrs, Volume= 1.1 af, Atten= 3%, Lag= 4.3 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 0.4 fps, Min. Travel Time= 2.3 min
 Avg. Velocity = 0.1 fps, Avg. Travel Time= 8.5 min

Peak Storage= 2,008 cf @ 12.17 hrs
 Average Depth at Peak Storage= 0.6'
 Bank-Full Depth= 1.0' Flow Area= 90.0 sf, Capacity= 44.5 cfs

40.00' x 1.00' deep channel, n= 0.100 Heavy timber, flow below branches
 Side Slope Z-value= 50.0 ' ' Top Width= 140.00'
 Length= 50.0' Slope= 0.0020 ' '
 Inlet Invert= 805.50', Outlet Invert= 805.40'



Summary for Reach 40R: Route 30 Ditch

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 4.50" for 100-Year event
 Inflow = 21.5 cfs @ 12.62 hrs, Volume= 3.4 af
 Outflow = 21.5 cfs @ 12.63 hrs, Volume= 3.4 af, Atten= 0%, Lag= 0.5 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Max. Velocity= 6.2 fps, Min. Travel Time= 0.4 min
 Avg. Velocity = 2.4 fps, Avg. Travel Time= 1.1 min

Peak Storage= 550 cf @ 12.62 hrs
 Average Depth at Peak Storage= 0.9'
 Bank-Full Depth= 2.0' Flow Area= 12.0 sf, Capacity= 116.0 cfs

2.00' x 2.00' deep channel, n= 0.035 High grass
 Side Slope Z-value= 2.0 ' ' Top Width= 10.00'
 Length= 160.0' Slope= 0.0459 ' '
 Inlet Invert= 662.34', Outlet Invert= 655.00'



Summary for Pond 20P: Culvert-2

Inflow Area = 51.0 ac, 0.04% Impervious, Inflow Depth > 3.73" for 100-Year event
 Inflow = 92.9 cfs @ 13.22 hrs, Volume= 15.9 af
 Outflow = 92.9 cfs @ 13.23 hrs, Volume= 15.8 af, Atten= 0%, Lag= 0.3 min
 Primary = 92.9 cfs @ 13.23 hrs, Volume= 15.8 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 685.38' @ 13.23 hrs Surf.Area= 1,594 sf Storage= 1,955 cf

Plug-Flow detention time= 0.7 min calculated for 15.8 af (100% of inflow)
 Center-of-Mass det. time= 0.7 min (921.7 - 921.0)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 681.00' | 3,164 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 681.00 | 4 | 0 | 0 |
| 682.00 | 67 | 36 | 36 |
| 683.00 | 203 | 135 | 171 |
| 684.00 | 591 | 397 | 568 |
| 685.00 | 1,137 | 864 | 1,432 |
| 686.00 | 2,328 | 1,733 | 3,164 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 681.50' | 12.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 681.50' / 681.00' S= 0.0143 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 684.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=92.7 cfs @ 13.23 hrs HW=685.38' (Free Discharge)
 1=Culvert (Inlet Controls 7.0 cfs @ 8.9 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 85.8 cfs @ 3.1 fps)

Summary for Pond 22P: Culvert-7

Inflow Area = 7.0 ac, 0.00% Impervious, Inflow Depth = 3.36" for 100-Year event
 Inflow = 21.5 cfs @ 12.21 hrs, Volume= 1.9 af
 Outflow = 29.8 cfs @ 12.22 hrs, Volume= 2.1 af, Atten= 0%, Lag= 0.6 min
 Primary = 29.8 cfs @ 12.22 hrs, Volume= 2.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 731.80' @ 12.20 hrs Surf.Area= 3,977 sf Storage= 6,013 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)
 Center-of-Mass det. time= (not calculated: outflow precedes inflow)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 728.00' | 6,013 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 728.00 | 457 | 0 | 0 |
| 729.00 | 1,190 | 824 | 824 |
| 730.00 | 2,606 | 1,898 | 2,722 |
| 731.00 | 3,977 | 3,292 | 6,013 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 728.20' | 18.0" Round Culvert L= 35.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 728.20' / 727.80' S= 0.0114 '/' Cc= 0.900 n= 0.012, Flow Area= 1.77 sf |
| #2 | Primary | 731.70' | 180.0' long x 4.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.38 2.54 2.69 2.68 2.67 2.67 2.65 2.66 2.66 2.68 2.72 2.73 2.76 2.79 2.88 3.07 3.32 |

Primary OutFlow Max=27.6 cfs @ 12.22 hrs HW=731.80' (Free Discharge)

1=Culvert (Inlet Controls 14.4 cfs @ 8.1 fps)

2=Broad-Crested Rectangular Weir (Weir Controls 13.2 cfs @ 0.7 fps)

Summary for Pond 23P: Culvert-3

Inflow Area = 4.7 ac, 0.20% Impervious, Inflow Depth = 2.69" for 100-Year event
 Inflow = 18.2 cfs @ 12.04 hrs, Volume= 1.1 af
 Outflow = 18.2 cfs @ 12.05 hrs, Volume= 1.1 af, Atten= 0%, Lag= 0.3 min
 Primary = 18.2 cfs @ 12.05 hrs, Volume= 1.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 708.39' @ 12.05 hrs Surf.Area= 863 sf Storage= 695 cf

Plug-Flow detention time= 0.7 min calculated for 1.1 af (100% of inflow)
 Center-of-Mass det. time= 0.7 min (846.3 - 845.6)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 706.00' | 3,590 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 706.00 | 23 | 0 | 0 |
| 707.00 | 120 | 72 | 72 |
| 708.00 | 571 | 346 | 417 |
| 709.00 | 1,324 | 948 | 1,365 |
| 710.00 | 3,126 | 2,225 | 3,590 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 706.00' | 12.0" Round Culvert L= 31.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 706.00' / 704.50' S= 0.0484 ' S= 0.0484 ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 708.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=18.1 cfs @ 12.05 hrs HW=708.38' (Free Discharge)

↑ **1=Culvert** (Inlet Controls 5.2 cfs @ 6.6 fps)

↓ **2=Broad-Crested Rectangular Weir** (Weir Controls 12.9 cfs @ 1.7 fps)

Summary for Pond 24P: Culvert-6

Inflow Area = 5.2 ac, 0.27% Impervious, Inflow Depth = 3.77" for 100-Year event
 Inflow = 19.5 cfs @ 12.17 hrs, Volume= 1.6 af
 Outflow = 19.2 cfs @ 12.20 hrs, Volume= 1.6 af, Atten= 1%, Lag= 1.8 min
 Primary = 19.2 cfs @ 12.20 hrs, Volume= 1.6 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 824.39' @ 12.20 hrs Surf.Area= 5,048 sf Storage= 3,355 cf

Plug-Flow detention time= 1.8 min calculated for 1.6 af (100% of inflow)
 Center-of-Mass det. time= 1.8 min (832.9 - 831.1)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 823.00' | 18,148 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 823.00 | 493 | 0 | 0 |
| 824.00 | 3,067 | 1,780 | 1,780 |
| 825.00 | 8,169 | 5,618 | 7,398 |
| 826.00 | 13,330 | 10,750 | 18,148 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 821.00' | 12.0" Round Culvert L= 57.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 821.00' / 820.50' S= 0.0088 ' S= 0.0088 ' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 824.00' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=19.2 cfs @ 12.20 hrs HW=824.39' (Free Discharge)

↑ **1=Culvert** (Barrel Controls 6.2 cfs @ 7.8 fps)

↓ **2=Broad-Crested Rectangular Weir** (Weir Controls 13.0 cfs @ 1.7 fps)

Summary for Pond 25P: Culvert-4

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 2.32" for 100-Year event
 Inflow = 14.1 cfs @ 12.12 hrs, Volume= 1.0 af
 Outflow = 14.0 cfs @ 12.12 hrs, Volume= 1.0 af, Atten= 1%, Lag= 0.3 min
 Primary = 14.0 cfs @ 12.12 hrs, Volume= 1.0 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 736.77' @ 12.12 hrs Surf.Area= 851 sf Storage= 849 cf

Plug-Flow detention time= 3.5 min calculated for 1.0 af (100% of inflow)
 Center-of-Mass det. time= 1.1 min (862.4 - 861.3)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 734.00' | 7,832 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 734.00 | 38 | 0 | 0 |
| 735.00 | 131 | 85 | 85 |
| 736.00 | 417 | 274 | 359 |
| 737.00 | 978 | 698 | 1,056 |
| 738.00 | 1,789 | 1,384 | 2,440 |
| 739.00 | 2,699 | 2,244 | 4,684 |
| 740.00 | 3,598 | 3,149 | 7,832 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 733.50' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 733.50' / 733.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 736.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=13.7 cfs @ 12.12 hrs HW=736.77' (Free Discharge)
 1=Culvert (Inlet Controls 6.3 cfs @ 8.0 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 7.4 cfs @ 1.4 fps)

Summary for Pond 26P: Depression

Inflow Area = 5.4 ac, 0.00% Impervious, Inflow Depth = 2.32" for 100-Year event
 Inflow = 13.7 cfs @ 12.14 hrs, Volume= 1.0 af
 Outflow = 13.7 cfs @ 12.14 hrs, Volume= 1.0 af, Atten= 0%, Lag= 0.0 min
 Primary = 13.7 cfs @ 12.14 hrs, Volume= 1.0 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs / 2
 Peak Elev= 722.14' @ 12.14 hrs Surf.Area= 234 sf Storage= 30 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (864.0 - 864.0)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 722.00' | 2,084 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 722.00 | 187 | 0 | 0 |
| 723.00 | 515 | 351 | 351 |
| 724.00 | 850 | 683 | 1,034 |
| 725.00 | 1,250 | 1,050 | 2,084 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 722.00' | 100.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64 |

Primary OutFlow Max=13.6 cfs @ 12.14 hrs HW=722.14' (Free Discharge)
 ↑1=**Broad-Crested Rectangular Weir**(Weir Controls 13.6 cfs @ 0.9 fps)

Summary for Pond 31P: Culvert-5

Inflow Area = 3.5 ac, 0.00% Impervious, Inflow Depth = 3.77" for 100-Year event
 Inflow = 15.6 cfs @ 12.10 hrs, Volume= 1.1 af
 Outflow = 15.0 cfs @ 12.14 hrs, Volume= 1.1 af, Atten= 4%, Lag= 2.5 min
 Primary = 15.0 cfs @ 12.14 hrs, Volume= 1.1 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 808.81' @ 12.14 hrs Surf.Area= 6,152 sf Storage= 3,352 cf

Plug-Flow detention time= 3.5 min calculated for 1.1 af (100% of inflow)
 Center-of-Mass det. time= 3.3 min (828.6 - 825.3)

| Volume | Invert | Avail.Storage | Storage Description |
|---------------------|----------------------|---------------------------|--|
| #1 | 806.00' | 19,462 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |
| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
| 806.00 | 184 | 0 | 0 |
| 807.00 | 306 | 245 | 245 |
| 808.00 | 517 | 412 | 657 |
| 809.00 | 7,488 | 4,003 | 4,659 |
| 810.00 | 22,117 | 14,803 | 19,462 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 806.00' | 12.0" Round Culvert L= 25.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 806.00' / 805.70' S= 0.0120 ' / Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf |
| #2 | Primary | 808.50' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir |

Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60
 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=14.8 cfs @ 12.14 hrs HW=808.80' (Free Discharge)

1=Culvert (Inlet Controls 5.7 cfs @ 7.3 fps)

2=Broad-Crested Rectangular Weir (Weir Controls 9.1 cfs @ 1.5 fps)

Summary for Pond 40P: Culvert-1 [Route 30]

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 4.50" for 100-Year event
 Inflow = 21.5 cfs @ 12.62 hrs, Volume= 3.4 af
 Outflow = 21.5 cfs @ 12.62 hrs, Volume= 3.4 af, Atten= 0%, Lag= 0.2 min
 Primary = 21.5 cfs @ 12.62 hrs, Volume= 3.4 af

Routing by Stor-Ind method, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs
 Peak Elev= 665.75' @ 12.62 hrs Surf.Area= 782 sf Storage= 389 cf

Plug-Flow detention time= 0.2 min calculated for 3.4 af (100% of inflow)
 Center-of-Mass det. time= 0.2 min (846.8 - 846.6)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 663.50' | 6,466 cf | Custom Stage Data (Prismatic) Listed below (Recalc) |

| Elevation (feet) | Surf.Area (sq-ft) | Inc.Store (cubic-feet) | Cum.Store (cubic-feet) |
|---------------------|----------------------|---------------------------|---------------------------|
| 663.50 | 5 | 0 | 0 |
| 664.00 | 13 | 5 | 5 |
| 665.00 | 94 | 54 | 58 |
| 666.00 | 1,006 | 550 | 608 |
| 667.00 | 2,797 | 1,902 | 2,510 |
| 668.00 | 5,115 | 3,956 | 6,466 |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|---|
| #1 | Primary | 663.10' | 12.0" Round Culvert L= 95.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 663.10' / 662.30' S= 0.0084 '/' Cc= 0.900 n= 0.012, Flow Area= 0.79 sf |
| #2 | Primary | 665.30' | 20.0' long x 20.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63 |

Primary OutFlow Max=21.4 cfs @ 12.62 hrs HW=665.75' (Free Discharge)

1=Culvert (Barrel Controls 4.9 cfs @ 6.3 fps)

2=Broad-Crested Rectangular Weir (Weir Controls 16.5 cfs @ 1.8 fps)

Summary for Link POA 1: SOUTHEAST

Inflow Area = 24.6 ac, 0.00% Impervious, Inflow Depth = 3.17" for 100-Year event
Inflow = 83.8 cfs @ 12.14 hrs, Volume= 6.5 af
Primary = 83.8 cfs @ 12.14 hrs, Volume= 6.5 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 2: WEST

Inflow Area = 84.1 ac, 0.04% Impervious, Inflow Depth > 3.70" for 100-Year event
Inflow = 139.3 cfs @ 12.11 hrs, Volume= 26.0 af
Primary = 139.3 cfs @ 12.11 hrs, Volume= 26.0 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA 3: NORTH

Inflow Area = 12.5 ac, 0.00% Impervious, Inflow Depth = 3.69" for 100-Year event
Inflow = 45.9 cfs @ 12.20 hrs, Volume= 3.8 af
Primary = 45.9 cfs @ 12.20 hrs, Volume= 3.8 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

Summary for Link POA-4: ROUTE 30

Inflow Area = 9.0 ac, 0.00% Impervious, Inflow Depth = 4.50" for 100-Year event
Inflow = 21.5 cfs @ 12.63 hrs, Volume= 3.4 af
Primary = 21.5 cfs @ 12.63 hrs, Volume= 3.4 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-30.00 hrs, dt= 0.05 hrs

APPENDIX B

Swale and Culvert
Calculations

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

Project: 117 Bliss Road Schoharie NY
Subject: Swale Calculations
Designed By DMA Date: 9/4/2019
Checked By DMA Date: 9/5/2019

Purpose:

To evaluate the capacity and velocity of each of the swales proposed for the project. The rational method $Q = CIA$ is used to determine the flow rate (in cubic feet per second) based on the Area (A), C Coefficient (C) of the surface type, and the Intensity (I) for a specific duration and storm frequency. The inputs and the calculations are entered into Hydraflow to determine rate of runoff (cfs) and velocity, amongst other values.

Inputs:

Using B type soils and a slope of > 6% on average the following C values are used.

| | |
|-----------------|---------------------|
| Forest | 0.18 |
| Meadow | 0.37 |
| Pasture | 0.45 |
| Farmland | 0.28 |
| Gravel road | 0.85 |
| Disturbed areas | 0.7 |
| Brush | 0.25 |
| Solar | 0.37 same as meadow |

Storm Event is 10 yr storm at 60 minutes duration = 1.55 inches/hour

This is based on Future Projections for a Changing Climate developed by Cornell University

N- coefficients for swales

| | |
|---------------------------|-------|
| Rock lined (6") = | 0.069 |
| Cobble bottom veg sides = | 0.033 |

Swale #1

240000

| A | C | I | CIA | |
|-------------------|------|-------------|-----|-----|
| 11900 gravel road | 0.85 | 1.55 | 0.4 | cfs |
| 222100 Farmland | 0.28 | 1.55 | 2.2 | cfs |
| 6000 Forest | 0.18 | 1.55 | 0.0 | cfs |
| 5.51 | | Total Swale | 2.6 | cfs |

| | |
|----------------------|-------|
| Top of Swale | 685.0 |
| Bottom of Swale | 663.2 |
| Length of Swale (lf) | 600 |
| Slope of Swale | 3.6% |

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

Project: 117 Bliss Road Schoharie NY
Subject: Swale Calculations
Designed By DMA Date: 9/4/2019
Checked By DMA Date: 9/5/2019

Swale #2

1250000

| A | C | I | CIA | |
|------------------|------|-------------|------|-----|
| 2620 gravel road | 0.85 | 1.55 | 0.1 | cfs |
| 264000 solar | 0.37 | 1.55 | 3.5 | cfs |
| 654380 Farmland | 0.28 | 1.55 | 6.5 | cfs |
| 329000 Forest | 0.18 | 1.55 | 2.1 | cfs |
| 28.70 | | Total Swale | 12.2 | cfs |

Top of Swale 685.0
Bottom of Swale 681.5
Length of Swale (lf) 131
Slope of Swale 2.7%

Swale #3 113800 2.612489

| A | C | I | CIA | |
|------------------|------|-------------|-----|-----|
| 3600 gravel road | 0.85 | 1.55 | 0.1 | cfs |
| 14500 solar | 0.37 | 1.55 | 0.2 | cfs |
| 77700 Farmland | 0.28 | 1.55 | 0.8 | cfs |
| 18000 Forest | 0.18 | 1.55 | 0.1 | cfs |
| 2.61 | | Total Swale | 1.2 | cfs |

Top of Swale 689.0
Bottom of Swale 681.5
Length of Swale (lf) 180
Slope of Swale 4.2%

Swale #4 26700 0.612948

| A | C | I | CIA | |
|------------------|------|-----------|-----|-----|
| 6900 gravel road | 0.85 | 1.55 | 0.2 | cfs |
| 12600 solar | 0.37 | 1.55 | 0.2 | cfs |
| 7200 Farmland | 0.28 | 1.55 | 0.1 | cfs |
| 0 Forest | 0.18 | 1.55 | 0.0 | cfs |
| 0.61 | | Sub Total | 0.4 | cfs |
| | | Total | 3.2 | |

Top of Swale 704.5
Bottom of Swale 690.0
Length of Swale (lf) 279
Slope of Swale 5.2%

Swales 5 and 6 discharge into
swale 4

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

Project: 117 Bliss Road Schoharie NY
Subject: Swale Calculations
Designed By DMA Date: 9/4/2019
Checked By DMA Date: 9/5/2019

Swale #5 173100 3.973829

| A | C | I | CIA | |
|------------------|------|-------------|-----|-----|
| 8000 gravel road | 0.85 | 1.55 | 0.2 | cfs |
| 143000 solar | 0.37 | 1.55 | 1.9 | cfs |
| 22100 Farmland | 0.28 | 1.55 | 0.2 | cfs |
| 0 Forest | 0.18 | 1.55 | 0.0 | cfs |
| 3.97 | | Total Swale | 2.3 | cfs |

Top of Swale 709.4
Bottom of Swale 705
Length of Swale (lf) 365
Slope of Swale 1.2%

Swale #6 21400 0.491276

| A | C | I | CIA | |
|------------------|------|-------------|-----|-----|
| 6120 gravel road | 0.85 | 1.55 | 0.2 | cfs |
| 6900 solar | 0.37 | 1.55 | 0.1 | cfs |
| 8380 Farmland | 0.28 | 1.55 | 0.1 | cfs |
| 0 Forest | 0.18 | 1.55 | 0.0 | cfs |
| 0.49 | | Total Swale | 0.4 | cfs |

Top of Swale 734.0
Bottom of Swale 706.0
Length of Swale (lf) 279
Slope of Swale 10.0%

Swale #7 285000 6.5427

| A | C | I | CIA | |
|-------------------|------|-------------|-----|-----|
| 11300 gravel road | 0.85 | 1.55 | 0.3 | cfs |
| 23500 solar | 0.37 | 1.55 | 0.3 | cfs |
| 91100 Farmland | 0.28 | 1.55 | 0.9 | cfs |
| 159100 Forest | 0.18 | 1.55 | 1.0 | cfs |
| 6.54 | | Total Swale | 2.6 | cfs |

Top of Swale 739.7
Bottom of Swale 729.0
Length of Swale (lf) 565
Slope of Swale 1.9%

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

Project: 117 Bliss Road Schoharie NY
Subject: Swale Calculations
Designed By DMA Date: 9/4/2019
Checked By DMA Date: 9/5/2019

Swale #8 92200 2.116621

| A | C | I | CIA | |
|------------------|-------------|------|-----|-----|
| 5480 gravel road | 0.85 | 1.55 | 0.2 | cfs |
| 0 solar | 0.37 | 1.55 | 0.0 | cfs |
| 24420 Farmland | 0.28 | 1.55 | 0.2 | cfs |
| 62300 Forest | 0.18 | 1.55 | 0.4 | cfs |
| 2.12 | Total Swale | | 0.8 | cfs |

Top of Swale 739.7
Bottom of Swale 733.5
Length of Swale (lf) 274
Slope of Swale 2.3%

Swale #9 143600 3.296602

| A | C | I | CIA | |
|-------------------|-------------|------|-----|-----|
| 15240 gravel road | 0.85 | 1.55 | 0.5 | cfs |
| 15700 solar | 0.37 | 1.55 | 0.2 | cfs |
| 31260 Farmland | 0.28 | 1.55 | 0.3 | cfs |
| 81400 Forest | 0.18 | 1.55 | 0.5 | cfs |
| 3.30 | Total Swale | | 1.5 | cfs |

Top of Swale 810.0
Bottom of Swale 733.5
Length of Swale (lf) 800
Slope of Swale 9.6%

Swale #10 227500 5.222681

| A | C | I | CIA | |
|-------------------|-------------|------|-----|-----|
| 15240 gravel road | 0.85 | 1.55 | 0.5 | cfs |
| 15700 solar | 0.37 | 1.55 | 0.2 | cfs |
| 115160 Farmland | 0.28 | 1.55 | 1.1 | cfs |
| 81400 Forest | 0.18 | 1.55 | 0.5 | cfs |
| 5.22 | Total Swale | | 2.3 | cfs |

Top of Swale 821.8
Bottom of Swale 809.0
Length of Swale (lf) 400
Slope of Swale 3.2%

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

Project: 117 Bliss Road Schoharie NY
Subject: Swale Calculations
Designed By DMA Date: 9/4/2019
Checked By DMA Date: 9/5/2019

Swale #11 59700 1.370523

| A | C | I | CIA | |
|-------------------|------|-------------|-----|-----|
| 14600 gravel road | 0.85 | 1.55 | 0.4 | cfs |
| 40600 solar | 0.37 | 1.55 | 0.5 | cfs |
| 4500 Farmland | 0.28 | 1.55 | 0.0 | cfs |
| 0 Forest | 0.18 | 1.55 | 0.0 | cfs |
| 1.37 | | Total Swale | 1.0 | cfs |

Top of Swale 874.0
Bottom of Swale 820.0
Length of Swale (lf) 766
Slope of Swale 7.0%

Channel Report

Swale #1

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 665.00
Slope (%) = 3.60
N-Value = 0.069

Highlighted

Depth (ft) = 0.54
Q (cfs) = 2.600
Area (sqft) = 1.41
Velocity (ft/s) = 1.84
Wetted Perim (ft) = 4.42
Crit Depth, Yc (ft) = 0.41
Top Width (ft) = 4.24
EGL (ft) = 0.59

Calculations

Compute by: Known Q
Known Q (cfs) = 2.60



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #2

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 681.50
Slope (%) = 2.70
N-Value = 0.033

Calculations

Compute by: Known Q
Known Q (cfs) = 12.20

Highlighted

Depth (ft) = 0.82
Q (cfs) = 12.20
Area (sqft) = 2.84
Velocity (ft/s) = 4.30
Wetted Perim (ft) = 6.19
Crit Depth, Yc (ft) = 0.86
Top Width (ft) = 5.92
EGL (ft) = 1.11



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #3

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 681.50
Slope (%) = 4.20
N-Value = 0.069

Highlighted

Depth (ft) = 0.36
Q (cfs) = 1.200
Area (sqft) = 0.75
Velocity (ft/s) = 1.60
Wetted Perim (ft) = 3.28
Crit Depth, Yc (ft) = 0.28
Top Width (ft) = 3.16
EGL (ft) = 0.40

Calculations

Compute by: Known Q
Known Q (cfs) = 1.20



Channel Report

Swale #4

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 690.00
Slope (%) = 5.20
N-Value = 0.069

Highlighted

Depth (ft) = 0.54
Q (cfs) = 3.200
Area (sqft) = 1.41
Velocity (ft/s) = 2.26
Wetted Perim (ft) = 4.42
Crit Depth, Yc (ft) = 0.45
Top Width (ft) = 4.24
EGL (ft) = 0.62

Calculations

Compute by: Known Q
Known Q (cfs) = 3.20



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #5

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 705.00
Slope (%) = 1.20
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 2.30

Highlighted

Depth (ft) = 0.65
Q (cfs) = 2.300
Area (sqft) = 1.92
Velocity (ft/s) = 1.20
Wetted Perim (ft) = 5.11
Crit Depth, Yc (ft) = 0.39
Top Width (ft) = 4.90
EGL (ft) = 0.67



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #6

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 706.00
Slope (%) = 10.00
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 0.40

Highlighted

Depth (ft) = 0.17
Q (cfs) = 0.400
Area (sqft) = 0.26
Velocity (ft/s) = 1.56
Wetted Perim (ft) = 2.08
Crit Depth, Yc (ft) = 0.15
Top Width (ft) = 2.02
EGL (ft) = 0.21



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #7

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 729.00
Slope (%) = 1.90
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 2.60

Highlighted

Depth (ft) = 0.62
Q (cfs) = 2.600
Area (sqft) = 1.77
Velocity (ft/s) = 1.47
Wetted Perim (ft) = 4.92
Crit Depth, Yc (ft) = 0.41
Top Width (ft) = 4.72
EGL (ft) = 0.65



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #8

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 733.50
Slope (%) = 2.30
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 0.80

Highlighted

Depth (ft) = 0.34
Q (cfs) = 0.800
Area (sqft) = 0.69
Velocity (ft/s) = 1.16
Wetted Perim (ft) = 3.15
Crit Depth, Yc (ft) = 0.22
Top Width (ft) = 3.04
EGL (ft) = 0.36



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #9

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 733.50
Slope (%) = 9.60
N-Value = 0.069

Highlighted

Depth (ft) = 0.33
Q (cfs) = 1.500
Area (sqft) = 0.66
Velocity (ft/s) = 2.28
Wetted Perim (ft) = 3.09
Crit Depth, Yc (ft) = 0.31
Top Width (ft) = 2.98
EGL (ft) = 0.41

Calculations

Compute by: Known Q
Known Q (cfs) = 1.50



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #10

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 809.00
Slope (%) = 3.20
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 2.30

Highlighted

Depth (ft) = 0.52
Q (cfs) = 2.300
Area (sqft) = 1.33
Velocity (ft/s) = 1.73
Wetted Perim (ft) = 4.29
Crit Depth, Yc (ft) = 0.39
Top Width (ft) = 4.12
EGL (ft) = 0.57



Channel Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Swale #11

Trapezoidal


Bottom Width (ft) = 1.00
Side Slopes (z:1) = 3.00, 3.00
Total Depth (ft) = 1.00
Invert Elev (ft) = 820.00
Slope (%) = 7.00
N-Value = 0.069

Calculations

Compute by: Known Q
Known Q (cfs) = 1.00

Highlighted

Depth (ft) = 0.29
Q (cfs) = 1.000
Area (sqft) = 0.54
Velocity (ft/s) = 1.84
Wetted Perim (ft) = 2.83
Crit Depth, Yc (ft) = 0.25
Top Width (ft) = 2.74
EGL (ft) = 0.34



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #1 - 40P

Invert Elev Dn (ft) = 662.30
Pipe Length (ft) = 85.00
Slope (%) = 0.94
Invert Elev Up (ft) = 663.10
Rise (in) = 18.0
Shape = Circular
Span (in) = 18.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Corrugate Metal Pipe
Culvert Entrance = Headwall
Coeff. K,M,c,Y,k = 0.0078, 2, 0.0379, 0.69, 0.5

Embankment


Top Elevation (ft) = 665.30
Top Width (ft) = 20.00
Crest Width (ft) = 20.00

Calculations

Qmin (cfs) = 4.04
Qmax (cfs) = 4.04
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 4.04
Qpipe (cfs) = 4.04
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 2.82
Veloc Up (ft/s) = 4.43
HGL Dn (ft) = 663.43
HGL Up (ft) = 663.87
Hw Elev (ft) = 664.21
Hw/D (ft) = 0.74
Flow Regime = Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #2 - 20P

Invert Elev Dn (ft) = 681.00
Pipe Length (ft) = 35.00
Slope (%) = 1.43
Invert Elev Up (ft) = 681.50
Rise (in) = 30.0
Shape = Circular
Span (in) = 30.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Concrete
Culvert Entrance = Square edge w/headwall (C)
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

Embankment


Top Elevation (ft) = 685.00
Top Width (ft) = 20.00
Crest Width (ft) = 14.00

Calculations

Qmin (cfs) = 19.82
Qmax (cfs) = 19.82
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 19.82
Qpipe (cfs) = 19.82
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 4.70
Veloc Up (ft/s) = 6.40
HGL Dn (ft) = 683.00
HGL Up (ft) = 683.01
Hw Elev (ft) = 683.79
Hw/D (ft) = 0.92
Flow Regime = Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #3 - 23P

Invert Elev Dn (ft) = 704.50
Pipe Length (ft) = 31.00
Slope (%) = 4.84
Invert Elev Up (ft) = 706.00
Rise (in) = 15.0
Shape = Circular
Span (in) = 15.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Concrete
Culvert Entrance = Square edge w/headwall (C)
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

Embankment


Top Elevation (ft) = 708.00
Top Width (ft) = 20.00
Crest Width (ft) = 20.00

Calculations

Qmin (cfs) = 3.00
Qmax (cfs) = 3.00
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 3.00
Qpipe (cfs) = 3.00
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 2.93
Veloc Up (ft/s) = 4.27
HGL Dn (ft) = 705.47
HGL Up (ft) = 706.70
Hw Elev (ft) = 707.01
Hw/D (ft) = 0.81
Flow Regime = Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #4 - 25P

Invert Elev Dn (ft) = 733.00
Pipe Length (ft) = 25.00
Slope (%) = 2.00
Invert Elev Up (ft) = 733.50
Rise (in) = 12.0
Shape = Circular
Span (in) = 12.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Concrete
Culvert Entrance = Square edge w/headwall (C)
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

Embankment


Top Elevation (ft) = 736.50
Top Width (ft) = 20.00
Crest Width (ft) = 20.00

Calculations

Qmin (cfs) = 2.20
Qmax (cfs) = 2.20
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 2.20
Qpipe (cfs) = 2.20
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 3.20
Veloc Up (ft/s) = 4.19
HGL Dn (ft) = 733.82
HGL Up (ft) = 734.13
Hw Elev (ft) = 734.47
Hw/D (ft) = 0.97
Flow Regime = Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #5 - 31P

| | | |
|---------------------|---|--------------------------------|
| Invert Elev Dn (ft) | = | 805.70 |
| Pipe Length (ft) | = | 25.00 |
| Slope (%) | = | 1.20 |
| Invert Elev Up (ft) | = | 806.00 |
| Rise (in) | = | 12.0 |
| Shape | = | Circular |
| Span (in) | = | 12.0 |
| No. Barrels | = | 1 |
| n-Value | = | 0.012 |
| Culvert Type | = | Circular Culvert |
| Culvert Entrance | = | Smooth tapered inlet throat |
| Coeff. K,M,c,Y,k | = | 0.534, 0.555, 0.0196, 0.9, 0.2 |

Embankment


| | | |
|--------------------|---|--------|
| Top Elevation (ft) | = | 808.50 |
| Top Width (ft) | = | 20.00 |
| Crest Width (ft) | = | 20.00 |

Calculations

| | | |
|---------------------|---|----------|
| Qmin (cfs) | = | 2.10 |
| Qmax (cfs) | = | 2.10 |
| Tailwater Elev (ft) | = | (dc+D)/2 |

Highlighted

| | | |
|-----------------|---|---------------|
| Qtotal (cfs) | = | 2.10 |
| Qpipe (cfs) | = | 2.10 |
| Qovertop (cfs) | = | 0.00 |
| Veloc Dn (ft/s) | = | 3.08 |
| Veloc Up (ft/s) | = | 4.12 |
| HGL Dn (ft) | = | 806.51 |
| HGL Up (ft) | = | 806.62 |
| Hw Elev (ft) | = | 806.92 |
| Hw/D (ft) | = | 0.92 |
| Flow Regime | = | Inlet Control |



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #6 - 24P

Invert Elev Dn (ft) = 820.50
Pipe Length (ft) = 57.00
Slope (%) = 0.88
Invert Elev Up (ft) = 821.00
Rise (in) = 18.0
Shape = Circular
Span (in) = 18.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Concrete
Culvert Entrance = Square edge w/headwall (C)
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

Embankment


Top Elevation (ft) = 824.00
Top Width (ft) = 20.00
Crest Width (ft) = 20.00

Calculations

Qmin (cfs) = 3.10
Qmax (cfs) = 3.10
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 3.10
Qpipe (cfs) = 3.10
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 2.27
Veloc Up (ft/s) = 4.06
HGL Dn (ft) = 821.58
HGL Up (ft) = 821.67
Hw Elev (ft) = 821.95
Hw/D (ft) = 0.63
Flow Regime = Inlet Control



Culvert Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Friday, Sep 6 2019

Culvert #7 - 22P

Invert Elev Dn (ft) = 727.80
Pipe Length (ft) = 35.00
Slope (%) = 1.14
Invert Elev Up (ft) = 728.20
Rise (in) = 18.0
Shape = Circular
Span (in) = 18.0
No. Barrels = 1
n-Value = 0.012
Culvert Type = Circular Concrete
Culvert Entrance = Square edge w/headwall (C)
Coeff. K,M,c,Y,k = 0.0098, 2, 0.0398, 0.67, 0.5

Embankment


Top Elevation (ft) = 731.70
Top Width (ft) = 20.00
Crest Width (ft) = 20.00

Calculations

Qmin (cfs) = 1.80
Qmax (cfs) = 1.80
Tailwater Elev (ft) = (dc+D)/2

Highlighted

Qtotal (cfs) = 1.80
Qpipe (cfs) = 1.80
Qovertop (cfs) = 0.00
Veloc Dn (ft/s) = 1.43
Veloc Up (ft/s) = 3.41
HGL Dn (ft) = 728.80
HGL Up (ft) = 728.71
Hw Elev (ft) = 728.89
Hw/D (ft) = 0.46
Flow Regime = Inlet Control



APPENDIX C

Rip Rap Apron
Calculations

Borrego Solar Systems, Inc.
55 Technology Drive, Suite 102
Lowell, MA 01851

| | | | |
|--------------|-----------------------------|-------|-----------|
| Project: | 117 Bliss Road Schoharie NY | | |
| Subject: | Rip Rap Apron Calculations | | |
| Designed By: | DMA | Date: | 8/28/2019 |
| Checked By: | DMA | Date: | 8/28/2019 |

Rational Method for calculating the size of the rip rap aprons.

Purpose:

To evaluate the size of the rip rap apron and stone size for each of the pipe outlets proposed for the project. The rational method $Q = CIA$ is used to determine the flow rate (in cubic feet per second) based on the Area (A), Coefficient (C) of the surface type, and the Intensity (I) for a specific duration and storm frequency. The inputs and the calculations are entered into . Hydraflow to determine rate of runoff (cfs) and velocity, amongst other values

Inputs:

Using B type soils and a slope of > 6% on average the following C values are used.

| | |
|-----------------|---------------------|
| Forest | 0.18 |
| Meadow | 0.37 |
| Pasture | 0.45 |
| Farmland | 0.28 |
| Gravel road | 0.85 |
| Disturbed areas | 0.7 |
| Brush | 0.25 |
| Solar | 0.37 same as meadow |

Storm Event is 10 yr storm at 60 minutes duration = 1.55 inches/hour

This is based on Future Projections for a Changing Climate developed by Cornell University

40P Culvert 1 (subcatchment 40)

| A (acres) | Description | C | I (inches/hr) | CIA | |
|-----------|-------------|------|---------------|------|-----|
| 0.05 | Dirt | 0.75 | 1.55 | 0.06 | cfs |
| 0.294 | gravel road | 0.85 | 1.55 | 0.39 | cfs |
| 2.028 | Farmland | 0.28 | 1.55 | 0.88 | cfs |
| 5.577 | Farmland | 0.28 | 1.55 | 2.42 | cfs |
| 0.27 | Forest | 0.18 | 1.55 | 0.08 | cfs |
| 0.8 | Forest | 0.18 | 1.55 | 0.22 | cfs |
| 9.019 | | | total 40P | 4.04 | cfs |

20P Culvert 2 (subcatchment 20)

| A (acres) | Description | C | I (inches/hr) | CIA | |
|-----------|----------------------|------|-----------------|-------|-----|
| 0.78 | brush | 0.25 | 1.55 | 0.30 | cfs |
| 5.137 | brush | 0.25 | 1.55 | 1.99 | cfs |
| 0.04 | gravel road | 0.85 | 1.55 | 0.05 | cfs |
| 0.616 | gravel road | 0.85 | 1.55 | 0.81 | cfs |
| 0.725 | meadow | 0.35 | 1.55 | 0.39 | cfs |
| 9.004 | meadow | 0.35 | 1.55 | 4.88 | cfs |
| 0.007 | Paved Parking (pads) | 0.95 | 1.55 | 0.01 | cfs |
| 4.974 | Farmland | 0.28 | 1.55 | 2.16 | cfs |
| 8.276 | Farmland | 0.28 | 1.55 | 3.59 | cfs |
| 1.046 | Forest | 0.18 | 1.55 | 0.29 | cfs |
| 8.268 | Forest | 0.18 | 1.55 | 2.31 | cfs |
| 38.873 | | | subtotal 20P | 16.79 | cfs |
| | | | total 20P + 24P | 19.82 | cfs |

23P Culvert 3 (subcatchment 23)

| A (acres) | Description | C | I (inches/hr) | CIA | |
|-----------|----------------------|------|---------------|------|-----|
| 0.128 | gravel road | 0.85 | 1.55 | 0.17 | cfs |
| 0.27 | gravel road | 0.85 | 1.55 | 0.36 | cfs |
| 2.912 | meadow | 0.37 | 1.55 | 1.67 | cfs |
| 1.274 | meadow | 0.37 | 1.55 | 0.73 | cfs |
| 0.01 | paved parking (pads) | 0.95 | 1.55 | 0.01 | cfs |
| 0.114 | farmland | 0.28 | 1.55 | 0.05 | cfs |
| 0.036 | Farmland | 0.28 | 1.55 | 0.02 | cfs |
| 4.744 | | | total 23P | 3.00 | cfs |

25P Culvert 4 (subcatchment 25)

| A (acres) | Description | C | I (inches/hr) | CIA | |
|-----------|-------------|------|---------------|------|-----|
| 0.674 | brush | 0.25 | 1.55 | 0.26 | cfs |
| 0.72 | brush | 0.25 | 1.55 | 0.28 | cfs |
| 0.288 | gravel road | 0.85 | 1.55 | 0.38 | cfs |
| 0.09 | gravel road | 0.85 | 1.55 | 0.12 | cfs |
| 0.285 | meadow | 0.35 | 1.55 | 0.15 | cfs |
| 0.108 | Farmland | 0.28 | 1.55 | 0.05 | cfs |
| 0.016 | Farmland | 0.28 | 1.55 | 0.01 | cfs |
| 2.728 | Forest | 0.18 | 1.55 | 0.76 | cfs |
| 0.489 | Forest | 0.18 | 1.55 | 0.14 | cfs |
| 5.398 | | | total 25P | 2.14 | cfs |

31P Culvert 5 (subcatchment 31)

| A (acres) | Description | C | I (inches/hr) | CIA | |
|-----------|-------------|------|---------------|------|-----|
| 0.085 | gravel road | 0.85 | 1.55 | 0.11 | cfs |
| 3.409 | meadow | 0.37 | 1.55 | 1.96 | cfs |
| 0.004 | farmland | 0.28 | 1.55 | 0.00 | cfs |
| 3.498 | | | total 31P | 2.07 | cfs |

24P Culvert 6 (subcatchment 24)

| A (acres) | Description | C | I (inches/hr) | CIA |
|-----------|----------------------|------|---------------|----------|
| 0.001 | gravel road | 0.85 | 1.55 | 0.00 cfs |
| 0.057 | gravel road | 0.85 | 1.55 | 0.08 cfs |
| 0.018 | meadow | 0.37 | 1.55 | 0.01 cfs |
| 5.082 | meadow | 0.37 | 1.55 | 2.91 cfs |
| 0 | paved parking (pads) | 0.95 | 1.55 | 0.00 cfs |
| 0.014 | paved parking (pads) | 0.95 | 1.55 | 0.02 cfs |
| 5.172 | | | total 24P | 3.02 cfs |

''

22P Culvert 7 (subcatchment 21)

| A (acres) | Description | C | I (inches/hr) | CIA |
|-----------|----------------------|------|---------------|----------|
| 1.27 | brush | 0.25 | 1.55 | 0.49 cfs |
| 0 | paved parking (pads) | 0.95 | 1.55 | 0.00 cfs |
| 0.26 | gravel road | 0.85 | 1.55 | 0.34 cfs |
| 0.73 | meadow | 0.37 | 1.55 | 0.42 cfs |
| 3.537 | forest | | | 0.00 cfs |
| 1.162 | farmland | 0.28 | 1.55 | 0.50 cfs |
| 6.959 | | | total 24P | 1.76 cfs |

| | | | | | | | |
|--|---|--------------------------------|-----------------------------------|--------------|--|-----------------------------|-----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 8/28/2019 |
| | | | | Checked By: | | DMA | Date: 8/28/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #2 | | | |
| | | | | | | | |
| D_o | = | 30 inches | | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 19.8 cfs | (10-Year Storm) | | | | |
| | | | From Rational Method Calculations | | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 28.5 feet | | | | | |
| Say | | 29.0 feet | | | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 36.5 feet | | | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | Assume T_w is 0.01' | | | | |
| d_{50} | = | 15.8 inches | | | | | |
| Say | | FALSE inches | | | | | |

| | | | | | | | |
|--|---|--------------------------------|--------|-----------------------------------|--|-----------------------------|-----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 8/28/2019 |
| | | | | Checked By: | | DMA | Date: 8/28/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #3 | | | |
| | | | | | | | |
| D_o | = | 15 | inches | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 3.0 | cfs | (10-Year Storm) | | | |
| | | | | From Rational Method Calculations | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 13.7 | | feet | | | |
| Say | | 14.0 | | | | | |
| | | | | | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 17.8 | | feet | | | |
| | | | | | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | | Assume T_w is 0.01' | | | |
| d_{50} | = | 3.2 | | inches | | | |
| Say | | 6.0 | | | | | |

| | | | | | | | |
|--|---|--------------------------------|--------|-----------------------------------|--|-----------------------------|-----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 8/28/2019 |
| | | | | Checked By: | | DMA | Date: 8/28/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #4 | | | |
| | | | | | | | |
| D_o | = | 12 | inches | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 2.1 | cfs | (10-Year Storm) | | | |
| | | | | From Rational Method Calculations | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 11.6 | | feet | | | |
| Say | | 12.0 | | feet | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 15.0 | | feet | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | | Assume T_w is 0.01' | | | |
| d_{50} | = | 2.8 | | inches | | | |
| Say | | 6.0 | | inches | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | | | | | | | |
|--|---|--------------------------------|--------|-----------------------------------|--|-----------------------------|-----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 8/28/2019 |
| | | | | Checked By: | | DMA | Date: 8/28/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #5 | | | |
| | | | | | | | |
| D_o | = | 18 | inches | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 2.1 | cfs | (10-Year Storm) | | | |
| | | | | From Rational Method Calculations | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 13.9 | | feet | | | |
| Say | | 14.0 | | | | | |
| | | | | | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 18.5 | | feet | | | |
| | | | | | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | | Assume T_w is 0.01' | | | |
| d_{50} | = | 1.5 | | inches | | | |
| Say | | 6.0 | | inches | | | |

| | | | | | | | |
|--|---|--------------------------------|--------|-----------------------------------|--|-----------------------------|-----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 8/28/2019 |
| | | | | Checked By: | | DMA | Date: 8/28/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #6 | | | |
| | | | | | | | |
| D_o | = | 12 | inches | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 3.0 | cfs | (10-Year Storm) | | | |
| | | | | From Rational Method Calculations | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 13.1 | feet | | | | |
| Say | | 13.0 | feet | | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 16.0 | feet | | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | | Assume T_w is 0.01' | | | |
| d_{50} | = | 4.4 | inches | | | | |
| Say | | 6.0 | inches | | | | |

| | | | | | | | |
|--|---|--------------------------------|-----------------------|-----------------------------------|--|-----------------------------|----------------|
| | | Borrego Solar Systems, Inc. | | Project: | | 117 Bliss Road Schoharie NY | |
| | | 55 Technology Drive, Suite 102 | | Subject: | | Rip Rap Apron Calculations | |
| | | Lowell, MA 01851 | | Designed By: | | DMA | Date: 9/6/2019 |
| | | | | Checked By: | | DMA | Date: 9/6/2019 |
| Borrego Solar | | | | | | | |
| Calculate Rip Rap Apron size for culvert outlets | | | | Culvert #7 | | | |
| | | | | | | | |
| D_o | = | 12 inches | | | | | |
| T_w | = | 0 | | | | | |
| Q | = | 1.8 cfs | (10-Year Storm) | | | | |
| | | | | From Rational Method Calculations | | | |
| L_a | = | $((1.7Q)/(D_o^{1.5}))$ | | | | | |
| L_a | = | 11.0 feet | | | | | |
| Say | | 11.0 feet | | | | | |
| W | = | $3D_o + L_a$ | | | | | |
| W | = | 14.0 feet | | | | | |
| d_{50} | = | $((0.02/T_w)(Q/D_o))^{4/3}$ | Assume T_w is 0.01' | | | | |
| d_{50} | = | 2.1 inches | | | | | |
| Say | | 6.0 inches | | | | | |